Internal Drive-Guided Embodied Behaviour Architecture for the Always-On Social Robot



Università di Genova

Nima Abaeian

DIBRIS - Department of Computer Science, Bioengineering, Robotics and System Engineering

University of Genova

Supervisors:
F. Rea, D. Pasquali, A. Sciutti, F. Mastrogiovanni

In partial fulfillment of the requirements for the degree of

Laurea Magistrale in Robotics Engineering

Declaration of Originality

I, Nima Abaeian, hereby declare that this thesis is my own work and all sources of information and ideas have been acknowledged appropriately. This work has not been submitted for any other degree or academic qualification. I understand that any act of plagiarism, reproduction, or use of the whole or any part of this thesis without proper acknowledgment may result in severe academic penalties.

Acknowledgements

This thesis was carried out in the CONTACT unit of the Italian Institute of Technology in Genova, and it depended on many people there.

I thank my supervisors, Francesco Rea, Dario Pasquali, Alessandra Sciutti, and Fulvio Mastrogiovanni from the University of Genova, for their guidance throughout this work. I owe a particular debt to Dario Pasquali. He built the always-on cognitive architecture this thesis extends and made room for a behaviour layer inside a system he had designed. I am also grateful to Giulia Belgiovine, Luca Garello, Omar Eldardeer and Carmine Miceli, whose work on that architecture is the ground this thesis stands on, and to Marco Gabriele Fedozzi, who helped me throughout this work and inspired it.

Finally, I thank the colleagues who shared their office with a hungry robot for eight days. They fed it, refused it when their role required, answered its messages and filled in the questionnaires, and every result in this thesis comes from what they did.

Abstract

An always-on robot can learn the social rhythm of a room over several days and still behave as it did on the first morning. The always-on cognitive architecture developed for the iCub segments a continuous audiovisual stream into episodes and recognises, without supervision, when a shared space is lively and when it is calm, yet its behaviour never draws on that knowledge. Its authors name what is missing: an action-selection loop that turns recognition into action, and a value system that defines what matters to the robot.

This thesis builds the loop, an embodied behaviour architecture that replaces the original behaviour module, and installs one value on it. The architecture tracks people as individuals and chooses whom to attend to from salience and learned affinity, while the robot's internal state sets the priority of what it does and says, in person and over Telegram. The value is a synthetic orexigenic drive: an energy reserve that drains with time and with every social act, and that only the people nearby can refill. Energy maintenance, which robots usually leave to a docking station or an operator, becomes part of the social exchange. Each regulatory outcome also updates a per-person affinity, so the robot remembers who fed it and favours them in later approaches.

An eight-day office deployment with twelve participants tested the loop. Deficit detection and behavioural redirection matched the design. Deficit was associated with more feeding in both phases; meals grew with deficit, and affinity changed approach eligibility. Recovery depended on caregiver presence; remote requests were rarely answered. Mean hunger ratings were below the midpoint for naturalness and genuineness and above it for helping motivation, without significant midpoint differences after correction. Helping motivation exceeded naturalness in an exploratory paired comparison. Written accounts identified repetitive, poorly timed requests and unchanging non-verbal expression. Regulatory effectiveness and credibility diverged. Both require evaluation, including how wording, timing and non-verbal expression shape credibility.

Contents

1 Introduction **1**
- 1.1 The always-on cognitive architecture inherited by this thesis . . . 1
- 1.2 An embodied behaviour architecture for drive-guided action . . . 7
- 1.3 Homeostasis and the synthetic orexigenic drive . . . 8
- 1.4 Contributions . . . 9
- 1.5 Research questions . . . 9
- 1.6 Structure of the thesis . . . 10

2 State of the Art **11**
- 2.1 Social cognition, interactional legibility, and non-verbal design . . . 11
- 2.2 Cognitive architectures for embodied and socially embedded agents 13
- 2.3 Attention, salience, and engagement selection . . . 15
- 2.4 Adaptation, memory, mutual learning, and personalisation . . . 16
- 2.5 Multimodal grounding and foundation-model-based HRI . . . 18
- 2.6 Homeostasis, allostasis, and drive-based artificial motivation . . . 19
- 2.7 Social expression and explanation of internal robot states . . . 22
- 2.8 The iCub ecosystem for cognitive and interaction architectures . . . 23

3 Methodology **25**
- 3.1 Architecture . . . 25
- 3.2 Multimodal perception and person-centred scene representation . . . 29
- 3.3 Salience-based attention selection and embodied gaze control . . . 31
- 3.4 Executive control: social-state orchestration and drive-gated behaviour logic . . . 34
- 3.5 Orexigenic homeostasis, homeostatic affinity learning, and adaptive social memory . . . 37
- 3.6 Remote interaction and human-mediated homeostatic loop closure 39
- 3.7 Experimental design and procedure . . . 40

4 Results **45**
- 4.1 Analytical scope . . . 45

4.2 Operational performance . . . 46
4.3 RQ1: Homeostatic functions . . . 46
4.4 RQ2: Recovery-oriented engagement and replenishment . . . 47
4.5 RQ3: Adaptive regulatory memory and its expression . . . 52
4.6 RQ4: Perceived naturalness and social embeddedness . . . 54

5 Discussion **58**
5.1 Recovery depended on who was present . . . 58
5.2 Attention and regulatory memory . . . 59
5.3 Effective but not credible . . . 59
5.4 How far the loop closed, and where this sits . . . 60
5.5 Limitations . . . 61

6 Conclusion **62**
6.1 What was asked and what was built . . . 62
6.2 Verdict on the research questions . . . 62
6.3 Contribution and broader impact . . . 63
6.4 Future work . . . 63

A Language-Model Prompts **66**
A.1 Embodied dialogue . . . 66
A.2 Remote dialogue on Telegram . . . 68

B Questionnaire Items **72**
B.1 Pre-experiment questionnaire . . . 72
B.2 Post-interaction questionnaire . . . 73

C Feeding Model Terms **74**

D Implementation Reference **75**
D.1 Vision-module output . . . 75
D.2 Controller constants . . . 75

References **77**

List of Figures

1.1 Always-on cognitive architecture. 2
1.2 Cognition as a system of coupled dynamical loops. 3
1.3 Shared-office validation of the always-on architecture. 6

3.1 The embodied behaviour architecture within the always-on architecture. 25
3.2 Overall system architecture. 27
3.3 Vision-module processing and output pipeline. 29
3.4 Salience arbitration. 32
3.5 Executive-control state transitions. 34
3.6 Synthetic orexigenic-drive dynamics. 38
3.7 Architecture use cases. 40
3.8 Physical experimental setup. 41

4.1 Observed feeding by hunger state and phase. 48
4.2 Mixed-effects model of feeding. 49
4.3 Recovery of observed Starving episodes and of days starting Starving. 50
4.4 Recorded orexigenic-drive dynamics. 51
4.5 Logged affinity histories by participant. 53
4.6 Affinity and recorded eligibility. 54
4.7 Semantic-differential domains and custom items. 55
4.8 Word-association ratings by respondent. 56

C.1 Posterior terms of the feeding model. 74

List of Tables

3.1 Principal functional layers of the embodied behaviour architecture. 28
3.2 Perception, identity and embodied gaze parameters. 30
3.3 Variables of the feeding model of Equation 3.23. 43

4.1 Recorded evidence by experimental phase. 45
4.2 Nominal meal choice by hunger state immediately before the feeding event. 50
4.3 Semantic-differential domain scores. 55
4.4 Perceptions of hunger and environmental integration. 57

D.1 Per-face schema published by the vision module on `landmarks:o`. 75
D.2 Controller constants and the reasoning behind each. 75

List of Acronyms

DAC	Distributed Adaptive Control
DoF	Degree of Freedom
GDPR	General Data Protection Regulation
GPT	Generative Pre-trained Transformer
HDBSCAN	Hierarchical Density-Based Spatial Clustering of Applications with Noise
HRI	Human–Robot Interaction
HRRL	Homeostatically Regulated Reinforcement Learning
IIT	Istituto Italiano di Tecnologia
IPS	Interaction Priority Score
iSEED	Interaction-oriented Situated Embodied Experience-Driven
JEPA	Joint-Embedding Predictive Architecture
JSON	JavaScript Object Notation
LED	Light-Emitting Diode
LLM	Large Language Model
NARS	Negative Attitudes toward Robots Scale
ONNX	Open Neural Network Exchange
OR	Odds Ratio
PnP	Perspective-n-Point
RGB	Red, Green, Blue
RoSAS	Robotic Social Attributes Scale
RPC	Remote Procedure Call
RQ	Research Question
SD	Standard Deviation
TDT	Token-and-Duration Transducer
UMAP	Uniform Manifold Approximation and Projection
YARP	Yet Another Robot Platform
YOLO	You Only Look Once

Chapter 1

Introduction

An always-on robot can watch a room for days, remember what happened in it and learn when it tends to be busy, and still behave exactly as it did on the first morning. The always-on cognitive architecture developed for the iCub by Pasquali *et al.* (2024, 2025) is such a robot. It segments a continuous audiovisual stream into episodes, stores them in an associative memory and recognises recurring social contexts without supervision. Its behaviour module, however, keeps tracking faces and otherwise wandering its gaze, whatever the memory has learned. Its authors name the two missing pieces themselves: an action-selection loop that turns recognition into action, and a value system that defines what matters to the robot and why (Pasquali *et al.*, 2025, 2026).

This thesis builds the first and supplies one example of the second. An embodied behaviour architecture replaces the inherited behaviour module and lets the robot's internal state change whom it looks at, whom it approaches and what it says. The value installed on it is a synthetic orexigenic (appetite-stimulating) drive: an energy reserve that drains over time and with every social act, and that only the people nearby can refill. Energy maintenance, which robots usually leave to a docking station or an operator, becomes part of the social exchange.

1.1 The always-on cognitive architecture inherited by this thesis

The inherited architecture comes from a research programme begun in *Artificial Cognition, from the Ground Up* (Pasquali *et al.*, 2024) and extended in *No Robot Is an Island* (Pasquali *et al.*, 2025). In its latest form, named iSEED (Interaction-oriented Situated Embodied Experience-Driven), this *always-on cognitive architecture* rests on three pillars, embodiment, memory and values, and is meant as a minimal testbed for how artificial cognition first emerges, not as a complete

system (Pasquali *et al.*, 2026). The agent has no explicit task. A curiosity-like proto-motivation turns it toward whatever departs from what it has recently perceived, since such departures may mark socially meaningful events. Where most current robotics relies on deep learning and large language models trained offline on large generic datasets (Pasquali *et al.*, 2025), the programme follows an *emergent enactive* methodology (Pasquali *et al.*, 2024; Sandini *et al.*, 2025): cognitive ability develops through the agent's own interaction with its environment instead of being built in beforehand.




Figure 1.1: Always-on cognitive architecture inherited by this thesis (Pasquali *et al.*, 2025). The diagram shows the original configuration with the SlowFast video encoder: multimodal perception and embodied behaviour contribute to event formation, episode segmentation detects novelty, and associative memory encodes and consolidates experience before returning a familiar or novel cluster assignment.

Pasquali *et al.* (2026) adopt the definition of cognition by Vernon (2014): "the process by which an autonomous system perceives its environment, learns from experience, anticipates the outcome of events, acts to pursue goals, and adapts to changing circumstances". It starts from a few innate (phylogenetic) abilities, not hand-crafted symbolic rules, and builds its own (ontogenetic) knowledge from experience. That knowledge serves one aim, internal consistency: keeping what the agent expects in line with what it perceives. It is also *altricial*: like a human infant, it depends on other social agents to develop, not on its own competences

alone (Pasquali *et al.*, 2026; Sloman & Chappell, 2005). The caregiver-mediated loop built in this thesis rests on that condition.

Rather than a single perception–action cycle, Pasquali *et al.* (2026) model cognition as several coupled dynamical loops running in parallel (Figure 1.2). Body and environment close one loop through overt action and perception, a body model and motivational dynamics another through covert action, internal simulation and sensory prediction. Where dual-process accounts fix the number of processing systems at two, Pasquali *et al.* (2026) hypothesise that a cognitive agent's foundational ability is to generate, sustain, close and make sense of such loops, which development extends across bodily, physical, social and temporal horizons. The architecture they validated filled only the lower loop: perception and overt gaze were in place and memory supplied temporal depth, but the motivational dynamics of the upper loop had no implementation and no path back to action. This thesis builds that path and gives the upper loop its first value.




Figure 1.2: Cognition as coupled parallel loops, reproduced from Pasquali *et al.* (2026) under CC BY. The lower loop couples body to environmental dynamics through overt action and perception; the upper couples a body model to motivational and attentional dynamics through covert action and sensory prediction.

The architecture ran on the *ICubHead*, the iCub's actuated head on a stationary 3D-printed upper body, with six degrees of freedom (DoF) in neck and eyes (Pasquali *et al.*, 2024, 2025). Two eye-mounted RGB cameras gave 640 × 480 video at 20 frames per second and an external miniDSP ambiMIK-1 microphone recorded 44.1 kHz stereo audio; the head also has a speaker and LEDs for facial expressions. Only perception and motor control ran on the head itself. Video

embedding and memory clustering ran on an external workstation (Intel Core i7 2.6 GHz, 16 GB RAM), linked to the head over the YARP middleware as a distributed, asynchronous network (Metta *et al.*, 2006; Pasquali *et al.*, 2025).

1.1.1 The global cognitive loop and modular architecture

The four modules form one continuous perception–action loop in spaces shared with people (Figure 1.1): what the robot senses turns its head, and the turn changes what it senses.

1. *Multimodal Perception* is the robot's minimal innate equipment for social awareness, modelled on early development: newborns attend to faces, sounds and biological motion, and infants engage in mutual gaze from about three months. Illumination is added to tell moments of the day apart (Pasquali *et al.*, 2025). From 20 Hz video frames and audio chunks the module extracts five features: visible faces (F), people gazing at the robot (mutual gaze), visual motion (M), illumination, and right and left audio root-mean-square amplitude (R, L). The implementation is deliberately coarse. Faces are counted from a separate object-recognition module's detections. Motion and audio register energy only, without separating biological from other movement or speech from other sound, so the design assumes people produce most of both. Raw audio and video are kept for later encoding.

2. *Embodied Behavior* steers the head according to an innate *social motive*, modelled on infants' tendency to seek other interactive agents. It tracks a face in view and otherwise alternates between resting and wandering its gaze over random points, both to search for faces and to widen the area it observes (Pasquali *et al.*, 2024, 2025). The head cannot manipulate objects, so its only actions are gaze shifts that serve exploration. YARP joint states tag every observation with the head posture it was made from.

3. *Episode Segmentation*, inspired by infants' search for novelty and regularity, cuts the stream into episodes: stretches of time during which the features stay close to their running averages. An *event* is a timestamped snapshot of the synchronised frame and audio chunk, the five features and the joint states; an *episode* is the sequence of events between two boundaries. The module tracks the running mean (μ) and standard deviation (σ) of F, M, R and L in the current episode, and an event with $|x_i - \mu_i| > 3\sigma_i$ sets that feature's outlier indicator ($\mathbb{I}_i \in \{0, 1\}$).[1] A boundary falls when

$$W_F \cdot \mathbb{I}_F + W_M \cdot \mathbb{I}_M + W_{AR} \cdot \mathbb{I}_{AR} + W_{AL} \cdot \mathbb{I}_{AL} \geq 0.5, \tag{1.1}$$

[1] Pasquali *et al.* (2026) report the criterion as a deviation of at least twice the modality

with fixed weights $W_F = 0.5$, $W_M = 0.25$ and $W_{AR} = W_{AL} = 0.125$. Faces carry half the weight, so a person arriving or leaving can close an episode alone. Motion and both audio channels carry the other half and must all be outliers together. This bias toward social events is deliberate. The closed episode is stored in a local SQLite database with its summary statistics and compressed media (.mp4, .wav), and the outlier event that closed it opens the next.

4. *Implicit Associative Memory* is modelled on infants' earliest memory, which links repeated episodes without recalling any one of them. It provides recognition (is the episode familiar, and to which cluster does it belong?) and temporal expectation (does it fit what usually happens at that time of day?). Both work by learning online as experience arrives and consolidating it offline later.

   Pretrained networks encode each closed episode. SlowFast (ResNet-50, Kinetics-400) maps the video to 400 action-class scores, VGGish maps each audio channel to 128 dimensions, and the channel-averaged audio vector joins the video vector in a 528-dimensional embedding. At the end of each day, or on demand in an induced resting state likened to a power nap, the embeddings are consolidated (Pasquali *et al.*, 2025). Uniform Manifold Approximation and Projection (UMAP) compresses them to 2D, Hierarchical Density-Based Spatial Clustering of Applications with Noise (HDBSCAN) finds dense clusters of any shape and labels outliers as noise (cluster -1), and a grid search picks the hyperparameters that maximise the silhouette score.

   Each new episode is then projected onto the learned manifold as soon as it closes and given a context label ($\ell_t \in \{-1, 0, 1, \dots\}$). After at least a day of operation, the memory also knows which cluster usually occurs in each time window, so it can expect the lively cluster during a midday coffee break and flag a mismatch when the live label differs.

1.1.2 Ecological validation and emergent context awareness

Pasquali *et al.* (2025) tested the pipeline in two multi-day deployments in real, unscripted settings:

- *Shared office:* Beside the lab's break area, the robot recorded 24 hours over four working days and segmented 449 episodes (Figure 1.3). Unsupervised,

mean. This account follows Pasquali *et al.* (2025), which specifies the validated segmentation in full and states the three-standard-deviation rule explicitly.



Figure 1.3: Shared-office validation of the always-on cognitive architecture. The ICubHead was positioned beside a break area (Pasquali *et al.*, 2025).

the memory settled on two clusters (silhouette score 0.69). A *lively* cluster had more faces, mutual gaze, motion and sound, with 91% of its episodes in the 1–1:30 PM coffee break; episodes between 1 and 2 PM averaged about a minute, against about 25 minutes otherwise. A *calm* cluster held longer episodes of an empty room or quiet desk work. Its episodes were also brighter, which the authors attribute to the wandering gaze settling on the window when no face was in view.

- *Conference:* In the Humanoids 2024 demonstration area in Nancy, the robot ran 15 hours over three days and segmented 2,304 shorter episodes (mean 15 s). Lively and calm clusters formed again (silhouette score 0.67); 61% of lively episodes fell between 2 and 4 PM, around the afternoon coffee break, and 75% of calm ones during talk sessions.

- *Both venues:* One memory built from both datasets told the venues apart with 98.7% accuracy and kept the lively–calm split within each.

Pasquali *et al.* (2026) then asked whether the clusters were stable enough to support expectation. Lacking external labels, they scored the memory against the agent's own goal of internal consistency: recognition accuracy (the same label in real time and after consolidation), temporal stability (the same label across days) and expectation consistency (the live context matching the one prior expe-

rience made most likely at that hour). In the office every measure improved with experience, recognition accuracy from 0.23 to 0.93 and expectation consistency from 0.24 to 0.96. At the conference the three measures diverged. Recognition (0.83, then 0.73) and stability (around 0.78) stayed above 0.7, but expectation consistency fell to 0.26 and then 0.08. A memory built from first-person experience inherits the regularity of the place that supplied it, and an exhibition hall with shifting schedules supplies little. A drive that must time its requests to human availability faces the same limit.

Dario Pasquali later refactored the architecture to run online (Section 3.1.3). VideoMAE replaced SlowFast, which cut latency and brought context inference into the live control path. The memory now has an online hippocampal path for rapid encoding and a neocortical module for long-term consolidation, so experience accumulates without pausing capture. This removes a limitation Pasquali *et al.* (2025) name themselves: recognition waited for an episode to close, so the context label lagged behind any interaction under way.

1.2 An embodied behaviour architecture for drive-guided action

A value system has no effect unless it can reach behaviour, and the inherited *Embodied Behavior* module offered no interface for it. This thesis therefore replaces that module with a behaviour layer through which any signal from the cognitive architecture, a motivational state or a recognised context, can change whom the robot attends to and what it says. Choosing an interaction partner requires telling people apart, and the inherited perception only counted faces, so I rewrote the vision module to track each person as an individual (Section 3.2). Attentional control selects whom to engage from perceptual evidence and learned per-person affinity, while executive control reads the robot's internal state to set the priority of regulatory behaviour. The resulting policy separates four kinds of behaviour by their trigger: reactive (a person greets the robot), proactive (a salient, eligible person is in view), expressive (the robot's hunger state) and remote (a hunger-state change, reported over Telegram). Apart from the vision module, perception, segmentation and memory still come from the surrounding always-on architecture.

The same layer supplies the action-selection loop that Pasquali *et al.* (2025) found missing and that Pasquali *et al.* (2026), whose validation was achieved *before* closing the action loop, place on their roadmap. An internal drive sets executive priority once an interaction starts, and the outcome of each interaction feeds back through affinity into the eligibility governing later target selection. None of these interfaces is specific to one need: a drive enters the layer by publishing a

state the executive controller can read and an outcome from which affinity can be learned, so curiosity or fatigue would travel the same path as hunger.

1.3 Homeostasis and the synthetic orexigenic drive

Pasquali *et al.* (2025) end their account by arguing that deciding what belongs in memory first requires defining what matters to the agent, and they name energy among the internal drives that could serve that role. Energy is the value installed on the new layer, and the choice is less arbitrary than it looks.

A social robot that runs out of energy stops being a social robot: face detection, dialogue and memory consolidation all stop with it. A review of long-term HRI studies finds that recharging which takes too long or comes at the wrong time constrains what the robot can do (Matheus *et al.*, 2025), and in a three-week office deployment it degraded the service users expected (Deshmukh *et al.*, 2018). An always-on architecture, which acquires its knowledge through uninterrupted immersion in a shared space, is especially exposed: every shutdown cuts the stream of experience the system learns from.

The conventional response treats energy as telemetry: a battery percentage is monitored, a threshold fires, and the robot either docks autonomously or waits for an operator to notice. Both options take the robot out of the interaction and give the people around it no role, although in a shared office or an exhibition hall those people already pay attention to it. With the new behaviour layer in place, the robot can ask them for energy instead of managing it silently.

Animals solved the problem of keeping a draining resource topped up long ago. Homeostasis is the self-regulating process that keeps an organism's internal environment within viable bounds while the outside world changes (Cannon, 1929). In a homeostatic system a deficit reorganises what the animal attends to and what it does next. Hunger narrows attention toward food-related cues (Petzschner *et al.*, 2021) and raises the priority of foraging over other pursuits. When several such variables compete, their relative urgency decides behaviour (Hulme *et al.*, 2019; Rosado *et al.*, 2022).

The mechanism proposed here is a synthetic *orexigenic homeostatic drive*. It rests on an energy resource that drains over time and with each social action the robot takes. When the resource leaves its preferred range, the gap acts as a regulatory error that reorders the priority of candidate actions. The term *orexigenic* names the role the variable plays: as the deficit grows, more of the robot's behaviour is directed toward getting fed. At critical depletion, feeding requests take precedence over ordinary social dialogue.

Pasquali *et al.* (2026) set a stricter test, causal grounding. A designer can impose constraints that reproduce value-consistent behaviour without the agent ever owning a value, so a value counts as grounded only if it forms through the agent's own experience. The orexigenic drive passes only part of that test (Section 5.4).

Because the behaviour available to a social robot is social, a deficit that recruits behaviour seeks replenishment through the people present, and energy maintenance becomes an HRI problem: as the internal state approaches its critical region, the robot asks for help in speech, or over Telegram when nobody is present, before depletion ends the interaction. Depending on people does not weaken autonomy, which here includes deciding when and how to seek help; a robot that cannot charge itself gains nothing by running down quietly.

1.4 Contributions

An adaptable embodied behaviour architecture. A behaviour layer replaces the fixed policy of the original *Embodied Behavior* module, keeps per-person memory across sessions and lets an internal state reshape attention, interaction eligibility and dialogue within the always-on perception–action loop. A rewritten vision module supplies the per-person observations it needs.

An operational value system. A synthetic orexigenic variable is installed on that layer. Its distance from the preferred range decides how much an event or action matters for regulation.

Action selection and loop closure. The layer coordinates reactive response, proactive initiation, embodied expression and remote contact according to the robot's social perception and internal need, with feeding requests taking priority in critical deficit. Energy regulation becomes a traceable HRI process: the robot asks for help, and a measurable recovery shows whether the help arrived.

Outcome-grounded social adaptation. Homeostatic affinities, learned per person, record who has fed the robot and bias later approaches, so regulatory outcomes enter social memory without blocking the escalation of critical requests.

1.5 Research questions

The thesis asks whether, once a behaviour layer is added to the always-on architecture, a single measurable internal drive can change both how iCub acts toward

people and what it learns from them. Showing that the robot can say it is hungry would validate neither the drive nor the layer that carries it. The criterion is whether the drive, acting through the behaviour architecture, changes action selection and produces recovery in a closed loop that can be traced in the logs. Purely reactive systems and scripted hunger displays fail this test, because no internal state changes what they select. Each link in the chain must stay visible in the data: detecting a deficit must lead to recovery-oriented action, that action must draw an observable response, the response must produce replenishment, and replenishment must alter later caregiver selection.

Regulatory effectiveness and human interpretation can still come apart: a robot might restore its energy efficiently while communicating poorly, or appear expressive while rarely getting fed. I therefore treat control validity, recovery success, adaptive memory and user perception as four levels of evidence, none of which can stand in for another, and ask one question per level.

RQ1. Does the orexigenic drive fulfil the core functions of classical homeostasis: internal monitoring, deficit detection, deficit-to-action conversion, and a change in how far interactions progress once a threshold is crossed?

RQ2. In an always-on social robot, does expressing an orexigenic deficit draw recovery-oriented help from people, and does that help restore the energy resource reliably, after every request?

RQ3. Does the robot's adaptive regulatory memory encode observed participant behaviour, and is that learned state subsequently expressed at the eligibility gate that governs proactive approach?

RQ4. In what ways does the behavioural expression of the orexigenic drive shape users' perception of the robot as a socially embedded and natural interaction partner?

1.6 Structure of the thesis

Chapter 2 reviews the prior work on which the design rests. Chapter 3 describes the architecture layer by layer and ends with the deployment protocol and statistical analysis. Chapter 4 reports the deployment against each research question in turn, Chapter 5 interprets the results and states their limits, and Chapter 6 answers the research questions and points to future work, mostly on the memory side of the always-on architecture. Four appendices give the language-model prompts, questionnaire items, fitted feeding model and an implementation reference.

Chapter 2

State of the Art

2.1 Social cognition, interactional legibility, and non-verbal design

Occupying the same room as a person does not make a robot socially embedded. Dautenhahn *et al.* (2002) define social embeddedness through structural coupling with a social environment: the agent's sensorimotor activity is shaped by an environment that contains other agents, and in turn changes it. Social signals added to a controller that otherwise ignores other agents do not meet this definition, so the design problem lies inside the controller. Henschel *et al.* (2020) frame HRI in the same spirit, as a setting in which people bring their own social-cognitive mechanisms to bear on what a robot does, and Sandini *et al.* (2025) add that mutual understanding rests on shared embodied cognition and accumulated first-person experience. The engineering requirement that follows does not assume the robot has human social cognition: its behaviour must let people infer what it is attending to, what it is trying to do, and how their own behaviour changes it.

Gaze is the channel where this requirement has been tested most. Admoni & Scassellati (2017) separate the literature into human-focused, design-focused, and technology-focused traditions. The split matters because the same head movement is a perceptual stimulus to one tradition, a design choice to another and controller output to a third. Mutual gaze signals availability and referential gaze establishes joint attention, while gaze aversion regulates conversational timing. Whether these functions transfer to a given robot depends on its body. Robots differ in eye articulation, head–eye coordination, field of view and how visible their gaze direction is, so findings from expressive virtual agents or from one eye mechanism do not automatically hold for another.

In a controlled hallway study, Fiore *et al.* (2013) found that a robot's proxemic behaviour, but not its gaze, altered perceived social presence and emotional

attribution: a robot that slowed and yielded scored higher than one that sped up and cut in front, and attributions grew over repeated passes whatever the proxemic condition. He *et al.* (2024) showed that gaze during navigation can also shape perceived social presence, but the preferred gaze depends on the scenario: a glance at the person is preferred where paths cross and adds little where they do not. Saunderson & Nejat's (2019) survey reaches a similar conclusion across body movement (kinesics), use of space (proxemics), touch (haptics) and timing (chronemics). Non-verbal behaviour affects how people frame an interaction, feel, respond and perform, but the effect depends on timing and context, and no single channel carries a fixed meaning.

This context-dependence is most visible when interaction begins. Lavit Nicora *et al.* (2024) treat gaze detection as a cue for starting collaboration in an assembly task, where gaze is evidence that a person is ready to coordinate. Abad-Moya *et al.* (2026) link such detection to legibility. Telling participants even a little about what the robot could perceive made them interpret its engagement responses more consistently, yet 11 of 15 participants still read the robot's orientation plus a short verbal acknowledgement as full engagement, although confirmed engagement came only with a later cue such as a change in LED state. A robot can classify an interaction correctly while still communicating its internal state poorly, so detecting a caregiver and selecting a recovery-oriented action are not sufficient. The robot's visible behaviour must make the energy request, and its urgency, clear on its own.

Time adds a different complication. From the Karotz Home Study, De Graaf, Ben Allouch, and van Dijk (2016) derive six phases of domestic acceptance, each ending in the user's decision to continue or stop, as the factors driving early adoption give way to others once novelty fades. Matheus *et al.* (2025) review this literature and argue for repeated evaluation in real settings over one-session impressions. An effect measured in a single session may be novelty alone.

Social embeddedness also has to survive absence. Marquardt *et al.* (2009) show that situated messages preserve spatial and contextual meaning even when human and robot are not co-present. A recovery architecture needs such a channel when no caregiver is physically available. A notification of battery percentage informs its reader; only a request that ties the robot's state to its consequence and to the help expected tells the reader what to do.

Legibility therefore depends on four things at once: what the robot perceives, when it acts, what its body can show and what people expect of it. The open problem is how to map changes in internal state reliably onto social acts that people can see and that arrive at the right moment.

2.2 Cognitive architectures for embodied and socially embedded agents

Modular HRI systems tend to postpone a hard integration problem: how perception, memory, motivation, learning, planning, and motor execution become parts of one continuing agent instead of stages in a pipeline of independent modules. Cognitive architectures address this problem by specifying how those functions constrain one another within an integrated control system (González-Santamarta *et al.*, 2025; Moulin-Frier *et al.*, 2018). For a socially embedded robot, the question is which architecture stays responsive while still supporting memory, internal valuation, anticipatory action and legible behaviour when interaction is uncertain.

Embodied and enactive approaches reject the idea that cognition can be specified apart from a body and its history. Georgeon & Ritter (2012) model emergent cognition through intrinsically motivated schemas whose meaning is constructed through interaction. This position takes on Harnad's (1990) symbol-grounding problem: a formal system cannot acquire intrinsic meaning by circulating symbols only among other symbols, so robotic concepts must ultimately be anchored in sensorimotor regularities, outcomes, and the agent's own organisation. Di Paolo (2003) extends the logic, arguing that adaptive, homeostatic organisation can ground intrinsic teleology, goals that belong to the agent and not to its designer, beyond a closed sensorimotor loop. On this reading, value is what makes a state or action matter to the agent at all, so it cannot be a layer added after perception.

Hybrid robotic architectures put this integration into practice. MERLIN2 (González-Santamarta *et al.*, 2025) generates, controls, plans and monitors behaviour by coordinating reactive, deliberative and emergent functions in one hybrid architecture, so planning is not the sole source of intelligent conduct. Fusaro *et al.* (2021) take a narrower but complementary route, modifying behaviour trees for human-aware cooperative planning by adding action costs and cost functions for the worker's availability, decisions and ergonomics. Behaviour trees are modular, easy to inspect and predictable in execution. Unless their transitions are linked to a valuation mechanism, their priorities stay where the designer set them.

DAC-h3 is built for proactivity from the outset. Moulin-Frier *et al.* (2018) integrate reactive control, adaptive learning, contextual knowledge and autobiographical representations in a layered Distributed Adaptive Control architecture that acquires and expresses knowledge about both world and self, so that proactive behaviour can arise from accumulated experience without an immediate trigger. DAC-h3 comes close to the required action-selection loop, but it is domain-general: it leaves open how a single energy-related drive should acquire salience, compete with social opportunities, and produce a socially legible request on iCub specifically.

Berto *et al.* (2025) make motivational structure testable in experiments. Their iCub architecture links sensing and perception to an intrinsic value system built from three drives (survival or recharging, affection or social comfort, and exploration or boredom reduction). By reweighting these drives they produced distinct Playful and Social robot profiles. Participants adjusted their own behaviour and attributed different traits to each profile without being told which was which. The result shows that value-system parameters can reorganise an interaction enough for human partners to infer distinct needs from it. The design also has clear limits: the drive set is small and hand-designed, and scalability, drive conflict, long-term learning, and safety under misclassification remain open.

A different lever comes from Carminatti *et al.* (2025), whose stress-inspired mechanisms on iCub alter deliberative functions (attention, memory, decision-making, cognitive flexibility) and leave goal selection itself untouched. For an energy-critical robot such modulation needs limits, since degrading deliberation too aggressively would make the robot least socially appropriate exactly when clear help-seeking matters most.

Emotion architectures joined drives, perception and expression earlier, under a different vocabulary. Kismet (Breazeal, 2003) connects affect recognition, drives, emotion dynamics, and expressive behaviour into one loop. Rodríguez & Ramos's (2015) review of computational emotion models finds the field still short on theoretical grounding, consistent operating cycles, tight coupling with cognition, cross-platform comparison, and validation. Moerland *et al.* (2018) show that emotion-like variables in reinforcement learning can shape exploration, risk, memory, and action selection. Together, these strands show that affective variables do computational work beyond making a robot look lively to an observer. They also warn against collapsing reward, valence, drive and expression into a single number.

Explainability adds a further architectural requirement. Stange *et al.* (2022) propose an explainable behaviour-generation architecture in which a social robot exposes its reasons for acting. A caregiver-mediated recovery system needs two kinds of explanation: behaviour people can read at once through posture, gaze or speech, and, when that reading is uncertain, a plain statement of what the robot lacks and what will happen without help. The value system and action-selection loop must therefore keep their state and priorities traceable. None of these architectures settles how continual context recognition should hand over to value-guided action.

2.3 Attention, salience, and engagement selection

Attention is how a robot reduces a high-dimensional stream of sensory events to a small set of candidates for action. In social HRI this is unusually hard, because what stands out perceptually is often not what matters for behaviour. A loud sound can be salient without being socially directed; a quiet caregiver entering the room can be the most important event in the scene while motion, speech and task-related stimuli are more salient.

Gaze is the external cue studied most in social HRI, and the work reviewed in Section 2.1 shows that it cannot be read apart from proxemics and context. As an input to the robot, gaze shows that social attention is more than face detection: the system must estimate whether a person is orienting toward the robot and whether context supports engagement at all. The robot's own kinematics limit how that estimate is formed and shown, which is why Shaghaghi *et al.* (2024) adapt a Social Gaze Space model specifically to iCub.

More recent work tackles stimulus competition directly. García-Martínez *et al.* (2025) use reinforcement learning for bio-inspired stimulus selection under multisensory overload in a social companion robot, replacing a fixed priority list with learned selection of whichever input should guide behaviour at that moment. Ghamati *et al.* (2025a) introduce a habituation-inspired gaze strategy paired with multi-objective Q-learning, so repeated or uninformative stimuli lose priority over time while socially relevant changes regain it. Both gain flexibility at a price: they depend on how the reward is specified and on training conditions that may not match the open-ended statistics of a real environment. A policy trained purely to maximise engagement can also conflict with self-maintenance just when energy is low, a conflict this literature does not address.

The always-on architecture of Pasquali *et al.* (2025) takes the opposite approach: its lightweight, non-adaptive front end reduces the scene to five aggregate features that feed a fixed gaze policy (Section 1.1.1). That keeps perception running cheaply, but salience stays almost entirely perceptual. The system can flag that something unusual happened without knowing whether the event is valuable, threatening, socially relevant, or useful for energy recovery. Section 2.8 returns to this gap, which calls for both an action-selection layer and a value system.

None of the systems above predicts whether an approaching person means to interact at all, the task the PAR-D dataset is built for (Thompson *et al.*, 2024). Abad-Moya *et al.* (2026) show that people draw on several modalities at once to attract a robot's attention, adapting their strategy once the system's detectable cues are disclosed. Raggioli *et al.* (2025) use deep reinforcement learning to learn approaching behaviour from user activity and disengagement, treating

social approach as a policy that must account for its likely effect on the person approached. Salience therefore cannot be determined from the robot's side alone: an interaction is worth starting when a person is available, receptive and well placed. Yet the robot may still need to act when those conditions are only partly met, because its deficit becomes urgent regardless of human readiness.

Salience thus has two sources. External social cues indicate who might be able and willing to help, while internal deviation indicates why that opportunity matters now. The approach and gaze studies reviewed above score candidates from external cues alone, with no input from the robot's own need.

2.4 Adaptation, memory, mutual learning, and personalisation

Adaptation is invoked constantly in HRI and defined precisely far less often. Ahmad *et al.* (2017) survey systems that adapt to user emotion, personality, behaviour, or interaction history across application domains. They find that most of the reviewed studies rest on short-term interactions, that no common protocol exists for evaluating adaptive robots, and that memory-based adaptation remains under-studied. In this thesis it means something narrower and testable: the robot's stored record of past encounters must reflect participant behaviour and must measurably change a later engagement decision.

Whether that requirement can be met depends on memory architecture. McClelland, McNaughton, and O'Reilly (1995) distinguish complementary learning systems, rapid episodic acquisition on one side and slower integration of regularities on the other. The distinction maps directly onto social robots: a single failed recharge interaction should be stored quickly, but a stable belief that one participant is usually responsive should emerge only after repeated evidence. Pasquali *et al.* (2024, 2025) follow the same split for always-on experience: episodes are stored as they close, and clustering consolidates them later.

Mutual-learning studies, all run on a simulated Reachy robot, show how a partner's behaviour enters what the robot learns. Lemhaouri *et al.* (2022) find that a caregiver's contingent responses shape affect-grounded language learning. Markelius *et al.* (2023) and Heikkinen *et al.* (2024) combine affect-grounded linguistic interaction with Differential Outcomes Training, in which each need, once met, earns its own distinct feedback. Across these studies the partner's timing, affect and consistency shape what the robot learns, so the partner is more than a source of labels. For caregiver-mediated energy recovery the precedent is direct, since assistance is an outcome of social coordination, and the robot's future behaviour should reflect how particular people have responded before.

Personalisation can target spatial, linguistic, behavioural, or preference parameters, and the literature spreads across all four. Patompak *et al.* (2020) learn personalised proxemics, since acceptable interpersonal distance varies with culture, traits, and familiarity. Pekarek Rosin *et al.* (2025) adapt HRI across diverse user groups by coordinating speech recognition, dialogue, and planning, and Tanevska *et al.* (2020) build social adaptation into a cognitive framework for iCub (Section 2.8). Wang *et al.* (2025) reduce how much feedback preference-based reinforcement learning needs by learning action representations. These methods differ in machinery but share two conditions: adaptation pays off when the inferred preference is stable enough to justify changing behaviour and the system can fall back to default behaviour if its preference model proves wrong.

Learning from engagement and disengagement bears directly on proactive help-seeking. Mihhailov *et al.* (2025) find that users provide more instruction when a robot's behaviour violates their existing model of it. Read with the approach learning reviewed above (Raggioli *et al.*, 2025) and with in situ teaching of social autonomy (Senft *et al.*, 2019), the finding suggests that correction, avoidance, delayed assistance, and successful support should enter memory as distinct signals, since a binary success flag would merge them.

Long-term studies explain why memory has to be evaluated across sessions. Beyond the acceptance studies reviewed in Section 2.1 (de Graaf *et al.*, 2016; Matheus *et al.*, 2025), the scoping review of Newman *et al.* (2025) shows that empathy-related interaction itself changes across repeated encounters. A policy that looks personalised within one session may only be reacting to cues available in that moment; personalisation is shown only when stored past interaction still changes later behaviour once the original cues are gone.

Adaptive preferences (Maroto-Gómez *et al.*, 2025) and stable motivational profiles (Berto *et al.*, 2025) can make a robot's history perceptible, but they describe personality, a property of the robot's parameters. Person-specific memory is a relation between the robot's experience and a particular partner.

Language models can maintain conversational continuity by summarising interaction history, but unconstrained text memory brings risks for privacy and factual accuracy (Ghamati *et al.*, 2025b; Pinto-Bernal *et al.*, 2025; Wang *et al.*, 2026b), and in a room with several people it can attach a remark to the wrong person. In a regulatory architecture, generative models can phrase what the robot says but should not decide who helped or whether replenishment succeeded.

Three requirements follow for memory-based adaptation. The stored representation must be compact and outcome-grounded, built from observable response and recovery variables, with no inferred sentiment. Its influence must be testable, so that later engagement differs measurably when the stored history differs. Adaptation must also stay subordinate to safety: the robot may prefer a historically responsive caregiver, yet it must escalate to other people or channels

once energy becomes critical.

2.5 Multimodal grounding and foundation-model-based HRI

Language is useful to an embodied robot only once it connects to perception, action and consequence, which is the symbol-grounding problem of Section 2.2 (Harnad, 1990). In HRI, grounding means three separate alignments. Words must refer to entities and events actually present in the environment. Plans must be limited to actions the robot can execute. Conversational claims about internal state must correspond to measured variables and controller decisions rather than to whatever a language model finds plausible to say next.

Allgeuer *et al.* (2024) tackle these alignments with a modular architecture that grounds an LLM in what the robot perceives and can do. It combines a chat manager with open-vocabulary object detection, pose estimation, gesture detection and other deep models to support open-ended conversation and collaboration. The modularity lets perceptual evidence and action interfaces constrain what the language model may generate. It does not remove the cost of integration: the architecture still coordinates models with different latency, uncertainty, and failure characteristics, so conversational competence is no guarantee of reliable execution under time-critical conditions.

LaMI takes a related route, splitting the problem into scene narration, planning, and expression (Wang *et al.*, 2024). Separating what the robot perceives from what it intends to do and from how it communicates reduces the burden on any single prompt. Kim *et al.* (2026) integrate LLM-based planning into modular robotic frameworks, and Kim *et al.* (2024) analyse how LLM-powered HRI changes dialogue, reasoning, task planning, and user experience. This work converges on placing foundation models inside a constrained architecture.

The reviews identify consistent limits. Wang (2026a) names multimodal integration, grounding, alignment, and real-time constraints as the central open challenges. Wang *et al.* (2026b) describe a field that is technically broad but uneven in method: user studies differ simultaneously in robot, task, prompting method, model version, and outcome measure, so reported gains in naturalness or task success rarely compare cleanly across papers. Pinto-Bernal *et al.* (2025) document design challenges around latency, reliability, and embodied context that do not disappear with a better model. Mauliana *et al.* (2025) extend evaluation across sessions, where conversational memory and expectation matter more than in a single encounter. Ghamati *et al.* (2025b) propose a personalised LLM agent for HRI. This work matters for remote communication and for voicing need naturally, but the critical control signal cannot depend on how fluently a

model generates text. The architecture must still be able to issue a fixed, verified recovery request when language generation fails.

ROMA streams audio, video and text in real time for interactive understanding and proactive monitoring (Tian *et al.*, 2026), and VideoMAE learns data-efficient self-supervised video representations for activity recognition (Tong *et al.*, 2022). Such models could sharpen recognition of caregiver availability, interaction onset, or response behaviour, but their value depends on computational cost, inference latency, hardware requirements, and robustness to distribution shift. Pasquali *et al.* (2025) choose lightweight perceptual features for these practical reasons: an always-on robot cannot assume unlimited compute.

Multimodal communication covers affect and non-verbal expression as well as vision and language. In the mutual-learning studies of Section 2.4, learning on both sides improved when each satisfied need earned its own sound and movement instead of one shared positive response (Heikkinen *et al.*, 2024; Markelius *et al.*, 2023), because the extra channel carried need-specific information. For expressing internal state, the matching requirement is that the channels agree: verbal urgency, gaze direction, posture, facial expression, and remote notification must signal the same state, or the redundancy turns into noise.

Remote communication faces the grounding problem of the situated messages discussed in Section 2.1 (Marquardt *et al.*, 2009). Foundation models can improve a remote channel by tailoring wording, summarising context, or choosing a suitable modality. They should not be allowed to invent the internal condition, suppress a critical alert, or select an unverified physical action. The division of labour is deliberately asymmetric: deterministic modules own measurement, thresholds, safety and action permissions, learned multimodal modules estimate social context, and generative models word the robot's messages within bounds the other two have set. Still unresolved is how these three kinds of module should exchange state with memory, the body and the running control loop.

2.6 Homeostasis, allostasis, and drive-based artificial motivation

Attention, memory and language give a robot the machinery of social action without giving it a reason to act. Physiology confronted the question of where such reasons come from long before robotics did. Cannon (1929) described the coordinated organisation through which open biological systems keep internal variables within viable ranges. The formulation is often reduced to fixed-point error correction, though even classical homeostasis concerns dynamic stability and never implied that internal variables stay fixed. Tinbergen's (1951) ethological account adds the missing behavioural mechanism: internal motivational states alter the

readiness of action systems, while external releasing stimuli determine when and how behaviour is expressed. This pairing of internal deficit with outside opportunity carried over into social robotics: Kismet's drives and triggering events draw on the same ethological models (Breazeal, 2003).

Allostasis keeps the vocabulary but changes the timing. Sterling (2012) argues that efficient regulation is predictive: instead of waiting for an error and then restoring a constant set point, the organism anticipates demand, reallocates resources in advance, and adjusts its own operating ranges. Schulkin & Sterling (2019) develop the brain-centred version, linking prediction, prioritisation, learning, and dopaminergic reinforcement. Hulme *et al.* (2019) survey the wider neurocomputational literature, in which internal-state control ranges from reactive feedback to model-based and predictive policies. Petzschner *et al.* (2021) draw a parallel distinction between reflexive control and flexible regulation informed by interoceptive context, experience, and expectation. For robotics, a homeostatic controller acts because a measured variable has already departed from a preferred range, while an allostatic controller acts because it predicts that inaction will produce a costly deviation later.

The free-energy and active-inference literature generalises the same idea with generative models of internal and external causes. It relates physiological regulation to variational dynamics (Bettinger & Friston, 2023), formalises how a system maintains its characteristic states (Friston *et al.*, 2023), and presents active inference as a single account of perception and action (Pezzulo *et al.*, 2024). These accounts give a principled way to combine uncertainty, prediction and preference, though empirical support varies sharply across specific predictive-processing claims (Hodson *et al.*, 2024). An architecture built around a single energy set point gains nothing from invoking active inference as a label: it would have to implement the generative model and test the predictions that follow, or the vocabulary would claim more than the architecture does.

Robotic homeostatic controllers offer more direct precedent. Cao *et al.* (2017a) combine homeostatic variables with reactive and deliberative layers in a collaborative social-robot controller, and a related end-user interface lets non-programmers configure homeostatic behaviour for NAO in robot-assisted social therapy (Cao *et al.*, 2017b). Both show that internal variables can drive socially observable action, and that authoring such behaviour need not require touching low-level code. Their shared limitation is that structure, thresholds, and behavioural repertoire are largely preconfigured: neither offers a general method for learning which social action will restore a given internal resource.

Guerrero-Rosado & Verschure (2021) propose a biologically inspired regulatory architecture grounded in the medial reticular formation and implement an initial robot model with simulated hunger and thirst. Ngo (2021) tests homeostatic and allostatic principles in a robotic model of desert-reptile regulation,

asking whether the controller reproduces the species' typical behaviour under environmental constraints. Rosado *et al.* (2022) focus on competition among drives, using mutually inhibitory neural populations to arbitrate efficiently among needs; their analysis of efficiency, fairness, and stability matters once more than one need can dominate action. A single orexigenic drive avoids instability between competing needs, but it still competes with ongoing social interaction, task commitments, and safety constraints, so its priority has to be graded.

For Di Paolo (2003), homeostasis is definitional: an agent is meaningfully adaptive only when it judges events by whether they preserve its own organisation. Pasquali *et al.* (2026) arrive at the same requirement from the direction of cognitive architecture: without an evaluative layer, a system can predict what may happen but cannot decide what should be pursued. Regulatory variables are attractive here because their state belongs to the agent, even when a designer has fixed the set point.

HRI research has also built artificial drives and related affective variables into social robots. Lewis & Cañamero (2016) separate hedonic quality from externally specified reward in a motivated robot (Section 2.7). Maroto-Gómez *et al.* (2018) propose a bio-inspired motivational decision system in which user perception feeds back into the robot's own motivational state. Later work from the same group adds biologically inspired decision-making, artificial biological functions, adaptive circadian rhythms, dopamine-like modulation, and adaptive object preferences with emotional responses (Maroto-Gómez *et al.*, 2023a,b,c, 2024, 2025).

Yoshida *et al.* (2025) link need to learned behaviour formally through homeostatically regulated reinforcement learning (HRRL), where reward is defined by drive reduction: an outcome is valuable when it moves the internal state toward its preferred region, aversive when it increases deviation. Under the paper's stated assumptions, learned policies minimise discounted future deviation. This ties drive reduction to optimal feedback control and predicts state-dependent value, risk aversion, competition between needs, and anticipatory regulation wherever predictive cues are available.

HRRL is a strong normative reference, but it settles fewer design choices than it appears to. Drive function, set point, discounting, state representation, action space, and available resources must still be specified by hand, and Yoshida *et al.* (2025) flag open questions of their own: storable resources, event-driven consumption, multiple timescales, biological realism, integration with active inference. An energy-centred approach has an advantage here: the energy variable is directly measurable and the replenishment outcome concrete, so drive reduction can be read directly from the log. The remaining difficulty is coordinating social recovery behaviour under a caregiver's uncertain availability.

Scheunemann *et al.* (2022) add that participants rated intrinsically motivated autonomous behaviour significantly warmer than a reactive baseline, suggesting

that behaviour driven from within can make a robot seem more like a social other. But intrinsic motivation is not automatically a benefit. Behaviour that originates inside the robot is also harder for a person to predict, whereas scripted behaviour can be made fully legible. The design target is therefore constrained autonomy: behaviour that originates in the robot's internal regulatory state while staying interpretable, safe, and responsive to the person in front of it.

The social environment adds norms that most resource-foraging models never face. A robot can have a strong energy deficit while the person nearby is engaged in a sensitive conversation, physically distant, or otherwise unavailable. Senft *et al.* (2019) address a version of this tension by letting people teach social autonomy in situ. This suggests a practical route: caregiver responses can shape the timing or choice of recipient without touching the hard safety requirement that a critical deficit must eventually be communicated to someone.

Together this work supplies the basis for an orexigenic drive. Classical homeostasis contributes monitoring, deficit detection and corrective action, allostasis adds anticipation, drive competition explains selection under conflict, and HRRL shows how internal improvement can define reward. None of it delivers the social recovery loop itself: an embodied robot that converts a measurable energy deficit into a proportionate request for human help, learns from how people respond to that request, and keeps a transparent link between internal state and outward conduct throughout.

2.7 Social expression and explanation of internal robot states

An internal variable matters in interaction only when its changes show up as behaviour a person can read and act on. That mapping decides whether a human can distinguish ordinary variation from a condition needing assistance, whether the robot's request is proportionate to its urgency, and whether the resulting response closes the regulatory loop. Kismet set the lasting pattern (Breazeal, 2003): facial and vocal behaviour there regulated the interaction by shaping caregiver response, which made expression part of control. Pre-authored displays (Cao *et al.*, 2017a,b) show the cost of the opposite choice: a display tied to a fixed threshold ignores interaction history and whether a caregiver is available.

Recharging research offers the most direct precedent for energy-centred recovery. After measuring how recharging degraded a robot's social service over three weeks in an office, Deshmukh *et al.* (2018) tested verbal strategies (transparency, apology, politeness) for managing user expectations during recharge, and these made the robot more acceptable while it charged. The work also reframes recharging as a visible social event that affects expectations, relationships and

perceived competence.

What should be expressed follows from the distinction between reward and hedonic quality. Lewis & Cañamero (2016) model basic pleasure as the direction and magnitude of homeostatic change, independent of any fixed outcome label, so the same event can be beneficial or harmful depending on current state. What is worth communicating is how far the robot is from its set point, where it is heading, and which action would reduce the deficit. A flat report that the battery is low conveys none of these. Because attention and confirmed engagement are distinct states, explanation has to back up expression wherever cues remain ambiguous (Abad-Moya *et al.*, 2026; Stange *et al.*, 2022).

Empathy research draws an ethical boundary here as much as an interactional one (Newman *et al.*, 2025; Park & Whang, 2022). A recovery-oriented robot can behave in a socially sensitive way without simulating suffering or manipulating guilt. The target is a request for care proportioned to the need, where the user understands the need and the consequence of inaction while keeping the freedom to decline.

Two outcomes must then be kept apart. Successful expression should help people notice the need, respond appropriately and bring about verified recovery, without excessive interruption or coercive urgency. Whether it also makes the robot seem natural is a separate question. Perception ratings such as the warmth reported by Scheunemann *et al.* (2022) and the naturalness reported by Maroto-Gómez *et al.* (2025) can reflect coherence, variability, anthropomorphic attribution or novelty. They do not reveal which internal mechanism participants understood, nor whether the behaviour obtained anything the robot needed.

2.8 The iCub ecosystem for cognitive and interaction architectures

iCub was designed around a specific research programme: cognition should be studied through development, sensorimotor experience and interaction on an open humanoid platform. Sandini, Metta, and Vernon (2007) present iCub as an open system for enactive cognition, and Metta *et al.* (2010) describe the mature platform as an open-systems testbed for cognitive development. Humanoid morphology, an articulated head and eyes, upper-body expressivity, tactile sensing, and the YARP middleware together make iCub suited to work in which perception, action, and social interpretation must be studied jointly.

The same features also limit the present results. Gaze is legible only through coordinated eye and head movement, so the direction of attention is harder to read than on a human face. Onboard computation is limited relative to contemporary foundation models, so processing is spread across external machines, at the cost

of added latency and dependence on infrastructure. The humanoid appearance raises user expectations that can far exceed actual autonomy. Rich embodiment makes iCub results valuable, yet they cannot be assumed to generalise to mobile service robots with different sensors, mobility, or expressive channels.

Fischer *et al.* (2018) address integration through iCub-HRI, a software framework for complex HRI scenarios that reduces the cost of combining perception, dialogue, and behaviour through reusable modules and interfaces. The contribution is infrastructural: complex scenarios become implementable, while what the robot should value during them is left open.

In the socially adaptable framework of Tanevska *et al.* (2020), an internal comfort level driven by the caretaker's stimuli guides iCub's social adaptation, and user studies compare adaptive with non-adaptive behaviour. Closest in spirit to a regulatory variable is the comfort drive of Mongile (2025), derived from attachment theory, which registers how pleasant iCub finds an interaction and steers its adaptation to the partner's interaction style. Users read the resulting behaviour as more goal-oriented and affective. With the drive profiles of Berto *et al.* (2025) and DAC-h3 (Moulin-Frier *et al.*, 2018), these frameworks show that iCub can carry the loop from internal variables to socially perceived action, though each implements a different part of it and evaluates it differently.

The Artificial Cognition programme of Pasquali *et al.* (2024, 2025) is the architecture this work builds on directly; Section 1.1 describes its implementation. Its strengths are sustained operation, situated first-person data, and self-supervised organisation of experience grounded in the robot's personal history. Its limitations define the present contribution. The system has no explicit goal beyond detecting novelty and regularity. Segmentation fragments high-activity periods. Memory has no separate short- and long-term dynamics and grows with no forgetting, reinforcement or value to decide which episodes to keep. Semantic information stays limited, and recognition never connects to action.

Pasquali *et al.* (2026) consolidate the programme as iSEED, promoting values to a pillar alongside embodiment and memory on the grounds that time, body and memory organise experience but do not decide how the agent behaves. Measured against their criterion of causal grounding, the face-weighted segmentation is only a proto-value system, sufficient to bias what gets remembered and no more. Section 1.3 sets out how the orexigenic drive answers that criterion.

Sandini *et al.* (2025) situate these developments within a broader programme of shared embodied cognition, arguing for architectures combining first-person experience, prospection, episodic memory, and social interaction. Morasso (2026) contrasts bio-inspired cognitive robotics with embodied AI, favouring socially acceptable, resource-aware intelligence over disembodied scale. Both support extending an always-on embodied architecture rather than moving all control inside a foundation model.

Chapter 3

Methodology

3.1 Architecture




Figure 3.1: Place of this thesis in the always-on cognitive architecture of Pasquali *et al.* (2025). The magnified view (top) expands the Multimodal Perception and Embodied Behavior modules (bottom) into the embodied behaviour architecture developed here. Episode segmentation and associative memory are inherited.

3.1.1 Design rationale

The *Embodied Behaviour Architecture* developed in this thesis replaces the exploratory *Embodied Behavior* module of the always-on cognitive architecture (Pasquali *et al.*, 2024, 2025), which had neither a value system nor action selection (Section 1.2). The new architecture splits embodied behaviour into four coordinated layers: salience-based attentional arbitration, executive dialogue gated by social state and drive, homeostatic self-regulation, and asynchronous remote outreach. Figure 3.2 shows the complete system.

Three things stay continuous across the layers. Each person keeps one track as they move. The robot's social and regulatory history with that person persists across sessions. The energy resource persists too, draining over time and by a fixed cost per social action. Two coupled loops build on this continuity. A 20 Hz sensorimotor loop turns the visual stream into fixation targets for the eyes and neck. A slower social and regulatory loop checks the deficit, starts proactive or reactive interactions, runs dialogue suited to the robot's state and updates social memory. The outcome of each interaction is credited to the person involved and sets the affinity that governs that person's later eligibility.

The organisation follows the open-system design of iCub, in which distributed perceptual and motor modules communicate through explicit middleware interfaces instead of one monolithic controller (Fischer *et al.*, 2018; Metta *et al.*, 2010). It also follows a socially embedded model of autonomy, in which people are regulatory partners whose significance to the robot develops through repeated interaction (Dautenhahn *et al.*, 2002). Because executive control and homeostatic regulation meet only at these interfaces, conversational policies and drive models can be developed independently.

In the configuration evaluated here, the synthetic orexigenic deficit is the value signal. An event counts as positive if it reduces the deficit and negative if it increases it.

3.1.2 Functional organisation

The system is an asynchronous network of modular services that communicate through YARP streaming ports and Remote Procedure Calls (RPCs) (Metta *et al.*, 2006). Camera frames, face records, speech events, drive telemetry, and meal payloads travel over streaming channels; RPCs handle one-off transitions such as starting an interaction, locking gaze, and enrolling an identity. Persistent drive, social, and experimental state is written atomically to JSON and SQLite stores.

Nominal update rates were 20 Hz for perception and attentional arbitration, 12.5 Hz for embodied gaze, 50 Hz for executive-state publication, 10 Hz for




Figure 3.2: Overall architecture of the always-on embodied behaviour system, showing perception, attentional selection, executive control, internal regulation, embodied output and the remote interaction channel.

remote-state processing, and 30 Hz for the Internal Drive Monitor, the touch-screen that displays the drive and also accepts meals (Figure 3.8). These are scheduler targets; actual throughput was limited by camera inference, message arrival and blocking input reads. Speech recognition ran per utterance, outside these fixed schedules. Table 3.1 lists what each layer does.

The architecture separates the *attention target* from the *interaction target*. The robot often tracks the most salient person in the room without speaking to them. The executive controller starts an interaction only when that person clears an eligibility threshold, set by social state and learned affinity, and the context-dependent cooldown has elapsed. The separation mirrors the distinction between attention and confirmed engagement drawn by Abad-Moya *et al.* (2026), and it keeps exploratory gaze shifts from turning into unsolicited conversations.

3.1.3 Coupling to always-on context memory

The embodied architecture runs alongside the refactored, online version of the always-on cognitive architecture (Pasquali *et al.*, 2025), which assigns contexts online (Table 3.1 and Section 1.1.2). The salience module reads this streaming context label $\ell_t \in \{-1, 0, 1\}$ to set how often the robot initiates interaction: the lively context (label 1) shortens the cooldown between approaches, the calm context (label 0) lengthens it, and unclassified noise (label -1) applies a default

Table 3.1: Principal functional layers of the embodied behaviour architecture.

Layer	**Primary input**	**Core transformation**	**Primary output**
Multimodal Perception	Camera frames and microphone audio	Face detection, identity tracking, pose and gaze estimation, speech transcription	Per-person observations, scene features and utterance events
Always-On Context Memory	Continuous audiovisual stream and segmented episodes	VideoMAE and VGGish encoding, online UMAP/HDBSCAN recognition and neocortical consolidation	Context label and persistent episode memory
Salience Network	Per-person observations, social memory and context	Salience computation, eligibility gating and target arbitration	Gaze target and proactive interaction request
Behaviour Orchestration	Selected person, speech, internal state and meal events	Social-state-conditioned behaviour and dialogue orchestration	Speech, facial expression, memory updates and interaction outcome
Internal Drive Model	Time, action costs and feeding	Continuous depletion, categorical hunger state and regulatory reward	Internal state supplied to physical and remote behaviour
Remote Channel	Internal state, learned affinity and Telegram messages	Drive-conditioned dialogue and recipient selection	Asynchronous social contact and requests for human assistance

(Equation 3.10). Context thus changes how often the robot reaches out, without altering any person's perceptual score or affinity.




Figure 3.3: Vision-module pipeline from YARP camera input through YOLO/ByteTrack identity tracking and MediaPipe pose estimation to per-face `landmarks:o` records and the selected target-box output.

3.2 Multimodal perception and person-centred scene representation

3.2.1 Perceptual objective

Social interaction requires a scene representation organised around people, in which location, presence over time, head orientation and readiness to communicate are tied to specific individuals. The baseline *Multimodal Perception* module (Pasquali *et al.*, 2024, 2025) tracked five aggregate features that did not distinguish between individuals (Section 1.1.1). With everyone present reduced to an anonymous count, a robot cannot ask a particular person for food, address a specific interlocutor or accumulate affinity toward anyone.

The vision module was therefore rewritten around individual people. It still computes the scene-level features and publishes them on the port the always-on memory reads, so episode segmentation receives the same features through the same interface as before. The gaze policy does differ: with no one in view the head now holds its last fixation instead of wandering, so the camera no longer sweeps the room and the scene those features describe changes accordingly. It processes 640×480 RGB frames and, when subscribers are connected, publishes one structured record per face on `landmarks:o`. Faces are detected in-process instead of being counted from a separate object-recognition module, then tracked and identified over time. Head pose, which the original module reduced to a count of people facing the camera, stays attached to each face. Appendix D.1 lists the published schema.

Table 3.2: Perception, identity and embodied gaze parameters.

Parameter	Value
Horizontal zone thresholds ($c_{x,i}/W$)	0.20, 0.40, 0.60, 0.80
Proximity zone thresholds (h_i/H)	0.10, 0.20, 0.40
Identity distance tolerance	0.62
Identity track retention	1.5 s
Identity re-evaluation interval	2.5 s
Max identity retries	3
Trajectory duration (eye, neck)	0.6 s
Reflex gains (vestibulo-ocular, oculo-collic)	1.3, 0.8

3.2.2 Face localisation, tracking and identity

Faces are found by the nano variant of the YOLO11 detector (YOLO11n) trained for faces, with a confidence threshold of 0.70, and each box is expanded by 10% per side. ByteTrack (Zhang *et al.*, 2022) tracks the boxes across frames and keeps a track alive through up to 120 processed frames of occlusion, 6 s at the nominal rate and about 20 s at the rate measured during deployment (Section 4.2). For bounding box $\mathbf{b}_i = (x_i, y_i, w_i, h_i)$ in a $W \times H$ image, the normalised centre $(c_{x,i}/W, c_{y,i}/H)$ and relative face height h_i/H describe position and apparent proximity independently of resolution; the zone thresholds in Table 3.2 bin them into five horizontal positions and four proximity classes.

Identity recognition matches 128-dimensional dlib facial embeddings against an enrolled gallery using combined minimum and median Euclidean distances. To suppress momentary misclassifications, a recognised name stays on its track through brief match failures, and a track still unknown is re-checked a limited number of times (Table 3.2). When a person tells the robot their name, the vision module saves one face crop under that name, overwriting any earlier one, and keeps at most five prototype embeddings in memory; after a restart, one embedding is rebuilt from the stored crop.

3.2.3 Head pose and gaze alignment

MediaPipe Face Landmarker extracts 478 3D landmarks per face: the 468-point face mesh plus 10 iris points. Head rotation $\mathbf{R}$ and translation $\mathbf{t}$ are estimated by Perspective-n-Point (PnP) optimisation over six standard facial points (nose tip, chin, eye corners, mouth corners):

$$\lambda_j \begin{bmatrix} u_j \\ v_j \\ 1 \end{bmatrix} = \mathbf{K} \begin{bmatrix} \mathbf{R} & \mathbf{t} \end{bmatrix} \begin{bmatrix} \mathbf{X}_j \\ 1 \end{bmatrix}. \tag{3.1}$$

Gaze alignment is the cosine between the head-forward vector $\mathbf{f}_i$ and the camera's optical axis $\mathbf{z}_c$:

$$g_i = \cos\theta_i = \frac{\mathbf{f}_i^{\mathsf{T}} \mathbf{z}_c}{\|\mathbf{f}_i\| \|\mathbf{z}_c\|}. \tag{3.2}$$

The camera is not calibrated: the intrinsic matrix $\mathbf{K}$ is approximated with $f_x = f_y = W$ and principal point $(W/2, H/2)$, and lens distortion is set to zero. The resulting g_i is a coarse proxy for whether the head faces the camera; it does not measure where the eyes look.

Alignments $g_i > 0.90$ count as mutual gaze, $0.70 < g_i \leq 0.90$ as near gaze, and lower values as averted gaze. MediaPipe landmarks are fused with YOLO bounding boxes through greedy one-to-one assignment on normalised centre distance, gated by centre containment and box overlap. A tracked face that MediaPipe misses is still published, with its orientation marked unknown.

3.2.4 Auditory and regulatory event streams

Speech is transcribed locally by the Parakeet TDT 0.6B model, run as a quantised ONNX network. Bookmark signals from the speech synthesiser mute microphone input while the robot speaks, so the robot never transcribes its own voice. Speech heard during a dialogue is attributed to the current interlocutor; a greeting heard outside any interaction starts a reactive interaction with the largest visible face. Meal messages from the feeding cards (Section 3.5.2) or the Internal Drive Monitor touchscreen carry increments of 10, 25 or 45 points and reach executive control through the same input stream.

3.3 Salience-based attention selection and embodied gaze control

3.3.1 From perceptual availability to interaction priority

Where the original gaze controller treated every face as equally urgent, the salience module gives each tracked person i an Interaction Priority Score (IPS) combining apparent proximity p_i, image centricity c_i and rectified gaze alignment a_i:




Figure 3.4: Salience arbitration from per-person perceptual features and social-memory gates to gaze selection and interaction initiation.

$$p_i = \min\left(1, \frac{h_i}{H}\right), \tag{3.3}$$

$$c_i = \max\left(0, 1 - \frac{\sqrt{(c_{x,i} - W/2)^2 + (c_{y,i} - H/2)^2}}{\sqrt{(W/2)^2 + (H/2)^2}}\right), \tag{3.4}$$

$$a_i = \max(0, g_i). \tag{3.5}$$

The unnormalised base priority is computed as:

$$I_i^0 = 0.50 p_i + 0.15 c_i + 0.50 a_i. \tag{3.6}$$

When several people compete, a habituation multiplier H_i scales the score; it is 1 for everyone except the current target (Section 3.3.3):

$$I_i = H_i \, I_i^0. \tag{3.7}$$

3.3.2 Social-state and affinity-dependent eligibility

Personalisation leaves the perceptual weights unchanged and acts instead on the eligibility threshold θ_i, which depends on social state s_i (Section 3.4.2) and learned homeostatic affinity $A_i \in [-1, 1]$:

$$\theta_i = \max\left(0.50, \theta_{s_i} - 0.15A_i\right), \tag{3.8}$$

$$(\theta_{\text{Unknown}}, \theta_{\text{Recognised}}, \theta_{\text{Greeted}}, \theta_{\text{Engaged}}) = (0.80, 0.65, 0.70, 0.85). \tag{3.9}$$

A person is eligible for proactive engagement when $I_i \geq \theta_i$; if the identity is still unresolved, the request waits up to 5 s for recognition to settle. Positive affinity lowers the threshold by up to 0.15, so the robot more readily approaches people who have fed it, and negative affinity raises it by as much. Repeated approaches are spaced by the context cooldown $T_{\text{cd}}(\ell_t)$:

$$T_{\text{cd}}(\ell_t) = \begin{cases} 3 \text{ s}, & \ell_t = 1 \quad \text{(lively)}, \\ 15 \text{ s}, & \ell_t = 0 \quad \text{(calm)}, \\ 5 \text{ s}, & \ell_t = -1 \quad \text{(fallback or noise)}. \end{cases} \tag{3.10}$$

3.3.3 Habituation, hysteresis and target stability

To stop gaze from flipping between equally salient people, the current target's score decays exponentially while a competitor stays in view, with τ counted from the end of the 5 s dwell:

$$H_i(\tau) = \exp(-\lambda\tau), \qquad \lambda = 0.06 \text{ s}^{-1}. \tag{3.11}$$

Gaze switches from the current target k to the challenger $j = \text{argmax}_i\, I_i$ only if

$$I_j > I_k + \delta \quad \wedge \quad t - t_{\text{switch}} \geq T_{\text{dwell}}, \tag{3.12}$$

with hysteresis margin $\delta = 0.10$ and minimum dwell $T_{\text{dwell}} = 5$ s. With no current target, gaze is assigned only when the highest score reaches 0.60. An active dialogue locks gaze to the interlocutor and overrides this arbitration.

3.3.4 Embodied target execution

The selected track is streamed to the vision module, which resolves its current box; the box centre is projected through the iCub gaze controller iKinGazeControl to a 3D fixation point $\mathbf{p}_t$ at fixed depth $z_0 = 0.7$ m:

$$\mathbf{u}_t = \begin{bmatrix} x_t + w_t/2 \\ y_t + h_t/2 \end{bmatrix}, \qquad \mathbf{p}_t = G_L(\mathbf{u}_t, z_0). \tag{3.13}$$

A motor command is sent only when the target moves beyond a pixel deadband:




Figure 3.5: Executive-control state transitions, showing proactive and reactive entry, social-state-conditioned behaviour, the Starving-state override, target monitoring and interaction completion.

$$\gamma_t = \mathbb{I}(|u_{x,t} - u_{x,t^-}| > 8 \ \vee \ |u_{y,t} - u_{y,t^-}| > 25)\,. \tag{3.14}$$

The FaceTracker module that sends these commands projects through the left-camera model (G_L), enables continuous iKin tracking, fixes neck roll at zero, leaves neck pitch free and disables saccades. Without a valid target it sends no neutral-pose command, so the last fixation holds until a new one replaces it.

3.4 Executive control: social-state orchestration and drive-gated behaviour logic

3.4.1 Interaction ownership and trigger modes

Executive control coordinates dialogue, speech synthesis and facial expressions, and only one interaction can own these resources at a time. Proactive requests (triggered by salience) and reactive greetings (triggered by unsolicited speech) enter the same finite-state machine. Proactive entry requires the person to answer the robot's greeting before the interaction continues; reactive entry skips that step, since the person has already spoken, and shortens the greeting and name exchange. In the state machine (Figure 3.5), every interaction first acquires ownership; only then does the branch that decides what is said take over.

3.4.2 Social state as interaction history

Social history with person i is described by three flags: whether the person is recognised (K_i), has been greeted today (G_i), and has completed at least one conversational turn today (T_i):

$$s_i = \begin{cases} \text{Unknown}, & \neg K_i, \\ \text{Recognised}, & K_i \wedge \neg G_i, \\ \text{Greeted}, & K_i \wedge G_i \wedge \neg T_i, \\ \text{Engaged}, & K_i \wedge G_i \wedge T_i. \end{cases} \tag{3.15}$$

An Unknown person gets an introduction and is asked for their name, a Recognised person gets a greeting by name, and a Greeted person gets open conversation.

3.4.3 Drive-gated behavioural policy

The hunger state $h \in \{\text{Disabled}, \text{Full}, \text{Hungry}, \text{Starving}\}$, where Disabled means the drive is switched off, decides which behaviour runs:

$$\pi(s,h) = \begin{cases} \pi_{\text{reg}}(s), & h = \text{Starving}, \\ \pi_{\text{Unknown}}, & h \neq \text{Starving} \wedge s = \text{Unknown}, \\ \pi_{\text{Recognised}}, & h \neq \text{Starving} \wedge s = \text{Recognised}, \\ \pi_{\text{Greeted}}, & h \neq \text{Starving} \wedge s = \text{Greeted}, \\ \pi_{\text{Greeted}}, & h \neq \text{Starving} \wedge s = \text{Engaged} \wedge I_i \geq \theta_i, \\ \pi_{\varnothing}, & \text{otherwise}. \end{cases} \tag{3.16}$$

Algorithm 1 spells out the Starving branch, its timeouts and when conversation resumes. All other states share the social-state branches of Equation 3.16, and Hungry differs from Full only through hunger-state prompt overlays (Section 3.4.4). Hunger never enters the IPS or eligibility equations: the Starving branch sets executive priority only once an interaction has started. Remote escalation is specified separately in Section 3.6.2.

3.4.4 Language-model instantiation

Embodied dialogue used Azure OpenAI GPT-4.1-mini, whereas Telegram dialogue used GPT-5-mini. Versioned templates in `prompts.json` supplied persona and hunger-state overlays (Appendix A). Embodied starter, reply, and wind-down

Algorithm 1 Behaviour-tree-equivalent social-state and drive-gated executive control

Receive either a proactive request or a reactive greeting event
if another interaction owns executive resources **then**
    Reject the new request
end if
Acquire interaction ownership and lock gaze to the selected person
Record initial social state, internal state and resource level
Start target-continuity monitoring
Priority selector:
if critical depletion is active **then**
    Request feeding
    Wait 8 s for a valid meal; retry once, then fail on a second consecutive timeout
    Acknowledge each meal and test whether Full has been restored
    Continue until Full, target loss, drive disablement or timeout failure
    if Full is restored and the interrupted branch was Greeted **then**
        Resume the conversational sequence
    end if
else
    if state is Unknown **then**
        Greet and require a response {reactive entry: skip the response requirement, the greeting already elicited one}
        Request and extract the name with one retry
        Enrol identity, acknowledge introduction and optionally continue to Greeted
    else if state is Recognised **then**
        Greet by name with at most two attempts, update memory and enter Greeted {reactive entry: one attempt, shorter timeout}
    else if state is Greeted **then**
        Generate a short opener
        Generate full replies for three turns, then brief acknowledgements
        Continue until silence, target loss or interruption
        Mark Engaged once at least one conversational turn is completed
    else if state is Engaged and again eligible **then**
        Execute the Greeted conversational branch while retaining Engaged memory
    end if
end if
Record final resource level, energetic cost and behavioural outcome
Release target and interaction ownership
Return the compact outcome to attentional learning

budgets were 40, 56, and 18 completion tokens; the corresponding Telegram reply, proactive-message, and summary caps were 800, 800, and 900. Sampling temperature was left at the service default.

3.5 Orexigenic homeostasis, homeostatic affinity learning, and adaptive social memory

3.5.1 Synthetic orexigenic drive

The synthetic orexigenic drive models an internal resource level $x(t) \in [0, 100]$, measured in stomach points (points hereafter). Without other input, x decays linearly at the passive rate $\rho = 100/(4 \times 3600)$ points/s, emptying a full reserve in 4 h. Each social action costs a discrete amount C_t, and each meal adds an increment M_t:

$$x_{t+\Delta t} = \mathrm{clip}_{[0,100]}\left(x_t - \rho\Delta t - C_t + M_t\right). \tag{3.17}$$

While the drive is enabled, the continuous level maps onto three states:

$$h(x) = \begin{cases} \text{Full}, & x \geq 60, \\ \text{Hungry}, & 25 \leq x < 60, \\ \text{Starving}, & x < 25. \end{cases} \tag{3.18}$$

Hungry lets the robot voice its need before the resource enters the critical Starving region, where feeding requests take priority over ordinary dialogue. Voicing need early is still not allostasis, which anticipates demand (Schulkin & Sterling, 2019; Sterling, 2012): this controller reads only the current level and forecasts neither depletion nor caregiver availability. The analogy with appetite is functional: stomach points and action costs measure neither metabolism nor real battery use. Figure 3.6 illustrates the resource dynamics. Action costs scale with verbal load: a greeting or a feeding acknowledgement costs 0.8 points, a name request or a feeding request 1.0, a conversation opener 1.2 and a full conversational turn 3.6.

3.5.2 Meal detection and attribution

Feeding cards, printed QR codes shown to the camera and read by the OpenCV QR detector in the vision module, were decoded every tenth frame. A card in view counted once and could count again only after it had gone undetected in three consecutive sampled frames. Executive control also applied a 3 s cooldown to all meal messages, from cards and touchscreen alike. During dialogue, an accepted




Figure 3.6: Synthetic orexigenic-drive dynamics, state thresholds, passive and action-dependent depletion, meal increments, homeostatic reward and affinity learning.

meal was attributed to the active interlocutor. Outside dialogue, a meal counted only if a face had been seen within the last 3 s, and affinity credit followed the current attention target.

3.5.3 Homeostatic reward and affinity learning

Net homeostatic reward across an interaction is $r = x_e - x_b$, where x_b and x_e denote the resource levels at its beginning and end. For interactions containing feeding, the credit $q = r + C_{\text{active}}$ adds back C_{active}, the summed cost of the robot's actions during the interaction, so the credit no longer contains those costs; without feeding, $q = r$. Passive decay stays in the credit. For an interaction of duration T with total meal input M, Equation 3.17 gives $q = M - \rho T$ when feeding occurs and $q = -\rho T - C_{\text{active}}$ when it does not, as long as x stays inside $[0, 100]$. Clipping at either bound moves the credit further from the nominal meal input. Dividing by a reference scale of 25 points gives the normalised update target $\bar{r}_i = \text{clip}_{[-1,1]}(q_i/25)$, which updates affinity A_i asymmetrically:

$$A_i^{(n+1)} = \begin{cases} \bar{r}_i, & q_i > \varepsilon \wedge u_i = 0, \\ \mathrm{clip}_{[-1,1]}\left[A_i^{(n)} + 0.25\left(\bar{r}_i - A_i^{(n)}\right)\right], & q_i > \varepsilon \wedge u_i > 0, \\ \mathrm{clip}_{[-1,1]}\left[A_i^{(n)} + 0.10\left(\bar{r}_i^{-} - A_i^{(n)}\right)\right], & q_i < -\varepsilon \wedge N_i < 2 \wedge M_i = 0, \\ A_i^{(n)}, & \text{otherwise}, \end{cases} \tag{3.19}$$

with neutral band $\varepsilon = 0.2$ points of credit (without a meal, $q_i = r_i$) and bounded negative target $\bar{r}_i^{-} = \max(-0.3, \bar{r}_i)$. Here u_i is the number of earlier affinity-changing updates of person i, so a person's first positive update overwrites the starting value. N_i and M_i are the conversational turns and meals of the interaction, so a negative update requires fewer than two turns and no meal. Positive evidence is integrated at rate 0.25 and negative evidence at 0.10. Affinity records an attributed regulatory outcome and carries no claim about the participant as a person.

3.6 Remote interaction and human-mediated homeostatic loop closure

3.6.1 Remote extension and prompt grounding

The asynchronous Telegram channel extends the robot's social reach beyond the people it can see (Figure 3.7). The effective remote state $h_{\text{eff}}(t)$ mirrors the hunger state h_r last published at time t_r and reverts to Disabled if no update arrives for more than $T_{\text{stale}} = 60$ s:

$$h_{\text{eff}}(t) = \begin{cases} h_r(t), & t - t_r \le T_{\text{stale}}, \\ \text{Disabled}, & t - t_r > T_{\text{stale}}. \end{cases} \tag{3.20}$$

System prompts depend on h_{eff}. In Full the robot does not raise hunger; in Hungry it mentions hunger at natural pauses, and the prompt forces a mention after three replies without one; in Starving it only asks, urgently, to be fed in person.

3.6.2 Stable transitions and proactive outreach

A remote state change takes effect only after it has held for $T_d = 60$ s:

$$\hat{h}(t) = h \quad \text{only if} \quad h_{\text{eff}}(\tau) = h \quad \forall \tau \in [t - T_d, t]. \tag{3.21}$$




Figure 3.7: Use-case diagram of the complete architecture, covering person perception, embodied attention, proactive and reactive spoken interaction, human-assisted internal-state regulation, and remote interaction through Telegram.

Subscribers are ranked by priority P_u, the learned affinity $A_{i(u)}$ of the person linked to account u, trusted only once that person has $n_{i(u)} \geq 3$ recorded interactions:

$$P_u = \begin{cases} A_{i(u)}, & n_{i(u)} \geq 3, \\ \varnothing, & n_{i(u)} < 3 \text{ or unresolved.} \end{cases} \tag{3.22}$$

In Hungry, the system contacts up to five subscribers with $P_u > 0.20$; in Starving, it sends its urgent request to all subscribers.

3.7 Experimental design and procedure

3.7.1 Study design and deployment

The architecture was evaluated during an eight-day naturalistic deployment in the main office of the IIT CONTACT unit in Genova, on an iCub Halfie (Figure 3.8). On each deployment day the always-on and behaviour architectures ran together online from 10:00 to 16:00. Phase 1 (4 days) assigned participants roles, so that the robot would meet both people who fed it and people who did not. Phase 2 (4 days) removed the roles. RQ1 to RQ3 are evaluated across both phases, with Phase 2 testing whether each effect held once nobody was following instructions; RQ4 rests on a questionnaire completed after Phase 2. Every controller constant




Figure 3.8: Physical experimental setup. Panel A identifies the remote-channel code, Internal Drive Monitor, local workstation, iCub Halfie, stereo microphone, feeding cards, network access point and window lighting. Panel B shows a typical interaction geometry and the speech-capture distance of about 0.4–1.0 m.

was fixed before deployment, and the thresholds, meal sizes, action costs and affinity parameters used in the analysis were checked against the controller source code. Most were derived from the session length and the drain rate instead of being tuned to data; Appendix D.2 gives the reasoning behind each. The remote channel did change once: Telegram notices on entry into Hungry were first sent on 18 June 2026, the day six Telegram templates were reworded to address one recipient privately (Appendix A).

Two classical criteria frame the evaluation. Monitoring the resource and restoring it through feeding test whether homeostatic feedback works (Cannon, 1929). Deficit-conditioned action and affinity-dependent eligibility test whether internal state modulates how ready the robot is to act (Tinbergen, 1951). Agreement between the logged resource dynamics and the programmed ones verifies that the controller ran as specified. Behavioural success is judged only from observed consequences; for recovery, that means a logged rise in x.

3.7.2 Participants and role conditions

Twelve adult participants enrolled (pseudonymised for analysis). Phase 1 assigned three roles by availability, not at random: Providers ($N = 2$, instructed

to feed frequently and respond promptly to remote alerts), Normal ($N = 8$, unconstrained voluntary interaction), and Non-Providers ($N = 2$, active daily interaction but prohibited from feeding). Phase 2 lifted these instructions without changing the cohort. All twelve attended at least one Phase 1 day and eleven attended at least one Phase 2 day, so every Phase 2 participant brought a Phase 1 role with them. Participants fed the robot with the feeding cards or the Internal Drive Monitor touchscreen.

3.7.3 Questionnaire instruments and ethics

The pre-interaction questionnaire collected demographics and a baseline on the 14-item Negative Attitudes toward Robots Scale (NARS) (Nomura *et al.*, 2006). The post-interaction questionnaire, given to all twelve participants after Phase 2, combined 15 Godspeed semantic differentials (naturalness, animacy, likeability) (Bartneck *et al.*, 2009), 12 RoSAS word associations on a 9-point scale (Carpinella *et al.*, 2017), 4 custom 5-point Likert items (hunger naturalness, hunger genuineness, belonging to the environment and motivation to help) and 4 open-ended prompts (Appendix B). The running system stored named face crops, Telegram chat identifiers and message text, and derived user profiles containing names, preferences, personal updates, and conversational style. Analytical exports replaced participant identities with pseudonyms. The study was approved under IIT ethics protocol `IIT_INT_HRI_rev02`, and participants gave informed consent under the GDPR.

3.7.4 Statistical framework and inference

Each outcome is counted in the unit that was directly observed: interactions for feeding and social-state outcomes, feeding events for meal choice, Starving episodes (reconstructed from the logged level) for recovery, hunger pings for remote replies, and logged target-selection records for the expression of affinity. Variation is inspected across phases and by leaving out one run or one named participant at a time. These ranges show how much any single run or person moves the result; they are not confidence intervals.

One exploratory model tests the deficit-to-feeding contrast: a Bayesian mixed-effects logistic regression. For interaction j of an enrolled participant, the binary outcome Y_j indicates whether at least one meal was received, and

$$\text{logit}[P(Y_j = 1)] = \alpha + \beta_D D_j + \beta_P P_j + \beta_{DP} D_j P_j + u_{i[j]} + v_{r[j]}, \tag{3.23}$$

where Table 3.3 defines each term and the identity and run intercepts are crossed.

Pooling Hungry and Starving targets the regulatory contrast without a separate coefficient for the few Starving interactions. The model uses the interactions

Table 3.3: Variables of the feeding model of Equation 3.23.

Role	Term	Meaning
Dependent variable	Y_j	Whether interaction j received at least one meal (1) or none (0).
Fixed effect (independent variable)	D_j	Deficit at interaction onset: Hungry or Starving (1) against Full (0). Hunger state arises from drain and action costs and was not assigned.
Fixed effect (independent variable)	P_j	Phase: Phase 2, with no roles (1), against Phase 1, with assigned roles (0). This is the one factor the design changed.
Fixed effect (interaction)	$D_j P_j$	Lets the deficit effect differ between phases.
Fixed effect (baseline)	α	Log-odds of feeding for a Full interaction in Phase 1, for an average person on an average day.
Random effect	$u_{i[j]}$	Intercept for each participant: some people feed more readily than others, and one person contributes many interactions.
Random effect	$v_{r[j]}$	Intercept for each run (deployment day): staffing, duration and time of day differ between days.

of the twelve enrolled participants: 23 interactions with unresolved identity and 14 belonging to two identities outside the roster are omitted. Role is left out of the model. The participant metadata fixed before analysis identifies only the two Providers and two Non-Providers, and the logs also contain identities outside the verified 12-person roster, so assigning all remaining identities to Normal would invent a design variable.

The model is estimated with Hamiltonian Monte Carlo using four chains, 2,000 warm-up iterations and 2,000 retained draws per chain. Fixed coefficients receive $\mathcal{N}(0, 1.5)$ priors on the log-odds scale; identity and run standard deviations receive half-normal $\mathcal{N}^{+}(0, 1)$ priors. Adjusted probabilities are posterior predictions standardised over the observed identities, runs and phase composition. Sampling was accepted only with $\hat{R} \leq 1.01$, bulk effective sample size above 400 and no divergent transitions; posterior predictive totals were compared with the observed feeding count. These estimates describe an adjusted association within this deployment. Figure 4.2 reports them, and Appendix C plots every fitted term.

Affinity effects on eligibility are recomputed exactly with the threshold rule of

the deployed controller (Equation 3.8). For every recorded candidate, the logged effective threshold is compared with the threshold the same social state would have at neutral affinity, with everything else held fixed. Entries into Starving are counted from the moment the logged level falls below 25. Segments that were already below 25 when recording began are counted separately. A return to Full counts as recovery only when feeding produces it, not when an operator switches the drive on or off (a mode reset, which sets the reserve back to 100) or when observation simply ends. Meal choice is analysed by the state just before feeding, whereas feeding incidence uses the state at the start of the interaction. A Telegram message within 15 minutes of a hunger ping (a remote hunger notification) counts as a time-matched response. Each message goes to the most recent unanswered ping, each ping takes at most one message, and a recovery notification closes the preceding request window. For RQ4, the respondent is the observation unit. The naturalness, animacy and likeability domains average items 1–5, 6–10 and 11–15 within each respondent; summaries report means and sample standard deviations, and Cronbach's α assesses their internal consistency. Permutation Wilcoxon signed-rank tests compare each domain with the neutral midpoint, with Holm correction across the three tests. The four custom items remain separate, with agreement defined as ratings of 4 or 5. Two-sided exact sign tests compare counts above and below the neutral midpoint of 3, omitting neutral ties and applying Holm correction across the four tests. An exploratory paired permutation Wilcoxon test contrasts helping motivation with perceived hunger naturalness; rank-biserial correlations report signed effect magnitude. Spearman correlations test whether baseline NARS scores track the three domains or the four custom outcomes. NARS measures general attitudes rather than a pre-test of the same perceptions. The p-values come from permutation, with Holm correction across seven correlations. Permutation procedures use 9,999 resamples with fixed random seeds. A sensitivity analysis excludes the respondent whose open response reports no interaction; otherwise open responses serve only to explain ratings. The RoSAS composites precomputed in the survey workbook are not validated factor scores, so the RoSAS word associations are reported item by item.

Chapter 4

Results

4.1 Analytical scope

The corpus comprises 217 interactions, 108 feeding events and 8 monitored runs, one per deployment day.

RQ1 to RQ3 report the two phases side by side, so that each effect can be checked with and without assigned roles (Section 3.7.1). The phases were not equally long (Table 4.1): 25.2 recorded hours against 20.9, so Phase 1 contributed more interactions, feeding events, depletion entries and affinity updates, while target-selection logging was almost balanced. Every result is therefore given as a rate on its own denominator, so that unequal exposure between the phases is not mistaken for a difference in effect.

Table 4.1: Recorded evidence by experimental phase. A candidate's selection row is logged once the cooldown has passed, and again when its identity, social state or eligibility changes or its score moves by 0.15, but at most once per second. Pings count issued notifications.

Recorded unit	**Phase 1**	**Phase 2**
Deployment days	4	4
Recorded hours	25.2	20.9
Interactions	134	83
Feeding events	73	35
Observed depletion entries	8	2
Affinity updates	129	76
Target-selection records	1,688	1,690
Hunger pings / matched messages	75/3	97/11

Questionnaire results describe the twelve respondents as a group and are never

related statistically to individual feeding or affinity histories, because the logs hold 14 named identities that cannot be matched one to one with the respondents.

4.2 Operational performance

The vision module processed frames containing a face at a median of 6.1 Hz, about a third of its 20 Hz scheduler target, and every downstream module received face records at that rate. Of 367 embodied conversational turns, 337 requested a language-model reply: 336 were generated. Generated replies reached speech dispatch a median of 1.56 s after the final transcript (interquartile range 1.32–1.91 s, maximum 6.96 s). The remaining 24 turns needed no generated reply, and 6 produced none.

4.3 RQ1: Homeostatic functions

4.3.1 Monitoring and deficit detection

The controller recorded 46.1 hours of resource dynamics over 8 runs. Of the 165,460 recorded samples, 164,469 were passive updates separated by a median of 1.00 s; the largest gap, 125.72 s, spans a same-day restart. Monitoring therefore ran whether or not anyone was interacting with the robot.

For all 217 interactions, the hunger state logged at onset matched the numerical level under the programmed boundaries of 60 points (Full–Hungry) and 25 points (Hungry–Starving). Over passive updates that did not hit the 0 or 100 bound, the observed drain was 25.0 points per hour against the programmed 25. The regulator thus tracked the resource as specified and passed the correct hunger state to the executive controller.

4.3.2 From deficit to action

The remote channel shows the gating first. Each of the 172 hunger pings was triggered either by entry into Hungry or by a proactive request issued while Starving, and none came from Full, as the controller is programmed to do. This verifies the gating and says nothing about the response. Whether anyone answered is a question for RQ2.

Face to face, the deficit changed how far interactions progressed. The interaction reached the Engaged state, the controller's completion state, in 79/114 Full interactions (69.3%) and 60/90 Hungry interactions (66.7%), but only 1/13 Starving interactions (7.7%). Full and Hungry barely differed; completion collapsed only below the Starving threshold. That is the pattern expected if the controller

reserves its strongest redirection, a feeding request that takes precedence over conversation, for critical deficit. By design, a Starving interaction reaches Engaged only if feeding restores Full and a conversational turn then follows (Algorithm 1). The logs do not show at which step the other Starving interactions ended.

Answer to RQ1. Monitoring ran continuously, deficit detection matched the programmed thresholds in every interaction, and the drive-gated policy (Equation 3.16) turned deficit into action, both remotely and face to face. Within this deployment, RQ1 is supported on all four functions it names.

4.4 RQ2: Recovery-oriented engagement and replenishment

4.4.1 Feeding in response to deficit

Feeding was uncommon when interactions began in Full and more frequent under deficit (Figure 4.1). Combining Hungry and Starving, 44/103 interactions received at least one meal, compared with 17/114 Full interactions. The absolute difference of 27.8 percentage points remained positive when any single run or named person was omitted, with leave-one-out differences ranging from 23.3 to 29.8 percentage points. These data show a within-deployment association between deficit and feeding.

In Phase 1, 27/57 deficit interactions received a meal (47.4%), compared with 10/77 Full interactions (13.0%), a 34.4 percentage-point difference. In Phase 2, the corresponding rates were 17/46 (37.0%) and 7/37 (18.9%), a difference of 18.0 percentage points. The Phase 2 Starving proportion rests on only 5 interactions, which is why its interval in Figure 4.1 is so wide.

Raw proportions treat every interaction as independent, yet the same people recur, and a person who feeds readily and happened to attend on a hungry day would inflate the contrast. The mixed-effects logistic model of Equation 3.23 (Section 3.7.4) corrects for this with random intercepts for person and run. It retains 180 interactions from the 12 enrolled participants across 8 runs, after the exclusions listed in Section 3.7.4.

Figure 4.2 gives the result. Standardised over the observed people and runs, the probability of a meal rose from 17.4% in Full to 53.0% in deficit during Phase 1, and from 21.5% to 44.5% during Phase 2. These are differences of 35.3 percentage points (95% credible interval 20.1–50.3) and 22.6 points (2.5–41.8). On the odds scale, deficit multiplied the odds of feeding by 6.33 in Phase 1 (2.77–15.20) and by 3.21 in Phase 2 (1.13–9.89). Both intervals lie above 1, so the deficit association held after the roles were removed. Its size may have shrunk.




Figure 4.1: Share of interactions that received at least one meal, by the hunger state in which the interaction began. Points are raw proportions, labels give the exact counts, and bars are 95% Wilson intervals.

Dividing the Phase 2 odds ratio by the Phase 1 odds ratio gives 0.51, but the interval (0.14–1.86) spans 1, so the data neither show a change between phases nor rule one out.

Figure 4.2 shows two rising lines, with the Phase 1 line steeper. The probability of a meal in a full robot is similar in both phases, so the phases differ in how far deficit lifts feeding, not in how often a satisfied robot is fed. In Phase 1 the intervals for Full and deficit do not overlap. In Phase 2 they touch at their edges, since that phase has fewer interactions. The contrast itself still excludes zero (2.5–41.8 points), because it is computed draw by draw from the same posterior, so the uncertainty the two probabilities share cancels out.

The random-intercept standard deviations were 0.77 on the log-odds scale for identity (95% credible interval 0.09–1.63) and 0.28 for run (0.02–1.00). People differed more than days did, and the run interval reaches almost to zero; both intervals are broad. Figure C.1 in Appendix C shows where that spread comes from. Most identity intercepts straddle zero. One person (P06) feeds more than average, with an interval that just clears zero, and the lowest intercepts (P03 and P11) lean the other way without clearly leaving it. People with only two to four interactions are pulled toward zero (partial pooling). The run intercepts all sit close to zero, so no single deployment day drives the deficit association. With 12 participants and 8 runs these spreads are imprecise and are not meant to rank people.

Sampling produced no divergent transitions, all $\hat{R}$ values were at most 1.000, and the minimum bulk effective sample size was 2000. The posterior predictive




Figure 4.2: Probability that an interaction received a meal, as estimated by the mixed-effects logistic model of Equation 3.23 after accounting for repeated people and runs. Deficit pools Hungry and Starving. Each line is one phase, and its slope is the deficit effect; bars are 95% credible intervals, and the labels give the two probabilities and the deficit odds ratio (OR) with its interval. Appendix C plots every fitted term.

95% interval of 44–75 feeding interactions contained the 58 observed among the retained records.

4.4.2 Meal choice under deficit

Meals grew larger as the deficit deepened, which is the direction regulation requires (Table 4.2). At the moment of feeding, 12 of 13 Starving meals were large and none was small. Hungry meals were more mixed, and half of the 16 meals delivered while Full were small.

The 108 meals supplied 3,225 nominal points but increased the recorded resource by 3,160.7 points because replenishment was clipped at 100. Of the 64.3 clipped points, 61.7 came from meals given while Full. Meals given under deficit lost only the remaining few points to the cap, so they restored the resource almost point for point.

4.4.3 Starving episodes and observed occupancy

The logged levels show 10 entries into Starving: 8 followed interaction cost and 2 followed passive drain. Phase 1 contained 8 entries and Phase 2 2, and every one of them later reached Full through feeding. This endpoint counts episodes, not

Table 4.2: Nominal meal choice by hunger state immediately before the feeding event.

State	Small (10)	Medium (25)	Large (45)
Full	8	5	3
Hungry	13	39	27
Starving	0	1	12

interactions: 6 of the 13 individual interactions that began in Starving received no meal.

Recovery time varied by almost three orders of magnitude (Figure 4.3). Across the 10 depletion entries, the median time from crossing into Starving to reaching Full was 65.6 s, with a range of 2.3–1,810.3 s. Entries caused by interaction cost recovered quickly: the Phase 1 median was 23.0 s across 6 episodes, and the Phase 2 median was 63.7 s across 2 episodes. The two passive-drain episodes lasted 294.8 and 1,810.3 s.




Figure 4.3: How long the robot stayed in critical deficit before feeding restored Full, the replenishment evidence for RQ2. Panel A plots time to Full for each of the 10 observed entries into Starving, coloured by what caused the entry, with marker shape giving the phase. Its logarithmic axis keeps recoveries of seconds and of hours on one scale. Panel B treats separately the 7 run-start segments that were already Starving when recording began.

A further 7 run-start segments were already Starving when recording began. The 3 in Phase 1 reached Full through feeding, whereas all 4 in Phase 2 ended through a mode reset.

Starving occupied 46.1 minutes, 1.67% of recorded run time, and 1.51% once

the initial Starving portion of run-start segments is excluded. Most of that time came from the two passive-drain episodes, during which nobody was present; they account for 75.8% of it. Figure 4.4 shows this concentration and marks feeding and mode events separately.




Figure 4.4: The resource level as logged on each of the eight deployment days, with hours counted from the day's first sample. Passive drain appears as the long downward slopes, action costs as small steps, and meals (green points) as jumps upward. Crosses mark mode events and the shaded band is the Starving region below 25 points.

4.4.4 Remote signalling

Within 15 minutes of a logged hunger ping, a user message followed in 14/172 cases: 3/75 in Phase 1 and 11/97 in Phase 2. The two phases sent different kinds of notification, because Hungry-entry notices were first sent on 18 June 2026. Phase 1 pings were mostly proactive Starving requests (62, with 3 matches) and only 13 Hungry-entry notices, none of them answered. Phase 2 pings were mostly

Hungry-entry notices (85, with 9 matches) and 12 proactive Starving requests (2 matches). Phase 2's higher reply rate therefore comes with a different mix of notifications, so the two rates do not compare like with like. The 14 matched messages arrived a median of 84.5 s after their ping, the fastest after 0.02 s and the slowest after 593.8 s.

Answer to RQ2. Feeding was associated with deficit in both phases, including after roles were lifted, but recovery was not reliable after every request. Meals grew with the deficit, and every observed depletion entry returned to Full. Yet 6 of the 13 Starving-onset interactions went unfed, only 14 of 172 remote pings drew a reply, and every Phase 2 segment that started Starving ended by a mode reset instead of feeding. The association supports recovery-oriented engagement within this deployment, without establishing a causal effect of hunger expression.

4.5 RQ3: Adaptive regulatory memory and its expression

4.5.1 Affinity update verification

Recomputing each of the 205 logged learning records with the affinity rule of Equation 3.19 reproduced its value with no numerical discrepancy and its outcome label in every case. The controller stores affinity under the exact spelling the face recogniser returns, so 2 people were held as several independent entries (for example, two spellings of one given name), whereas the delivered log carries one name per person. I separated the entries by following each update's starting value. This gives 17 memory keys, each matching a stored key exactly in number of updates and final value. The event table omits the update counter that decides whether a positive update is a person's first, so I checked all 74 positive events against both permitted branches. 6 of them match only the first-update branch.

Affinity was formed in both phases: 129 updates were logged in Phase 1 and 76 in Phase 2. Final stored affinity spanned -0.01 to 0.93 across the 17 memory keys, with a median of 0.48 (Figure 4.5).

4.5.2 Expression in recorded eligibility decisions

For each of 3,378 named target-selection records, the logged effective threshold equalled $\max(0.50, \theta_s - 0.15A_i)$ and the eligibility flag agreed with the comparison between IPS and that threshold. Against the neutral-affinity threshold, 88 records were eligible with their recorded affinity but would have stayed below it; 1 record




Figure 4.5: How the robot's learned affinity for each of the 12 enrolled participants moved with the logged updates, the encoding half of RQ3. The 2 logged identities outside the roster have 15 updates between them and are not drawn. Faint dots mark every update. A meal lifts affinity and an unrewarded approach lowers it (Equation 3.19), so single updates zigzag within a day; the line joins the end-of-day value with a smooth monotone curve. For people held under several spellings, the panel shows only the entry with the most updates, and the other entries add 10 updates that are not drawn. Each deployment day gets an equal slot, marker colour gives the phase, and the heavier vertical line marks the phase boundary. Positive values lower that person's eligibility threshold, and Figure 4.6 shows where this changed a decision.

showed the reverse under negative affinity, and every other record received the same decision under both thresholds (Figure 4.6).

Of the records that affinity made eligible, 59 fell in Phase 1 and 29 in Phase 2; the single restriction occurred in Phase 1. Affinity therefore kept changing eligibility decisions after the roles were removed. These counts are logged records, not distinct approaches, since one approach opportunity can be logged several times (Table 4.1).

Answer to RQ3. The adaptive memory stored attributed regulatory outcomes exactly as programmed, and the stored state changed eligibility decisions in both




Figure 4.6: Where learned affinity decided whether the robot could approach someone, the expression half of RQ3. Each point is one of 3,378 named target-selection records. The horizontal axis gives how far its Interaction Priority Score fell above or below the threshold at neutral affinity, and the vertical axis gives how much affinity lowered that threshold. Records right of the diagonal were eligible. The 88 green records passed only because of affinity, and the single red record was blocked by it. Grey and blue records would have been decided the same way without affinity.

phases. RQ3 is supported for both encoding and expression.

4.6 RQ4: Perceived naturalness and social embeddedness

RQ4 rests on the questionnaire of Section 3.7.3, which measures perceived naturalness, social embeddedness and caregiving motivation separately because they need not move together.

4.6.1 General perception of the robot

All 12 respondents completed every numerical item. Their mean age was 29.1 years (SD = 5.16, range 24–44), 8 were men and 4 women, and all had met a robot before: 8 regularly, 2 many times and 3 a few times, with one participant marking two categories.

Three five-item semantic-differential domains yielded the scores in Table 4.3, and none differed from the neutral midpoint after Holm correction. Descriptively,

likeability sat above the midpoint and naturalness below it: participants leaned toward liking the robot without judging it natural or humanlike. Figure 4.7 shows the respondent-level spread behind those means, wide for likeability (SD 1.08) and tighter for naturalness (SD 0.77).

Table 4.3: Semantic-differential domain scores on a 1–5 scale ($N = 12$). α denotes Cronbach's alpha.

Domain	M (SD)	α	p_{Holm}
Naturalness / humanlikeness	2.50 (0.77)	.86	.193
Animacy / responsiveness	2.97 (0.80)	.82	.514
Likeability	3.52 (1.08)	.95	.283




Figure 4.7: How the 12 respondents judged the robot and its hunger (RQ4). Panel A shows each respondent's mean on the three semantic-differential domains, with the group mean and standard deviation and a dashed line at the neutral midpoint of 3. Panel B shows every answer to the four custom items, from 1 (dark red, strong disagreement) to 5 (dark blue, strong agreement), with each bar centred on its neutral ratings.

Figure 4.8 shows the twelve nine-point word associations. *Happy* was the only descriptor above the midpoint of 5 ($M = 5.33$). The other social and emotional words sat below it: *Social* (4.50), *Feeling* (3.83), *Emotional* (3.83) and *Compassionate* (3.25). Threat-related descriptors were near the floor: *Aggressive* ($M = 1.08$), *Dangerous* (1.33) and *Scary* (1.92). *Strange* and *Awkward* both averaged 4.08, close to *Social*. Participants saw a happy, harmless robot, but not a strongly social or emotional one, and found it about as strange as it was social.




Figure 4.8: The twelve RoSAS descriptors on their nine-point scale, ordered by mean, with light markers for individual ratings, diamonds for means and bars for medians. The dashed line marks the midpoint of 5. Only *Happy* lies above it, and the threat words sit near the floor.

4.6.2 Interpretation of the orexigenic drive

Only 1 of 12 respondents found the hunger expression natural and 2 found it genuine, although 7 respondents agreed that it motivated helping and 6 felt the robot was part of the environment (Table 4.4). For none of the four custom items was the balance between agreement and disagreement significant after Holm correction (all adjusted $p \geq .500$). One respondent reported being unable to interact with the robot despite completing the ratings. Excluding that record left the descriptive pattern unchanged, and no test became significant (smallest adjusted $p = .281$).

Within respondents, helping motivation exceeded hunger naturalness by a mean of 1.08 scale points (SD = 1.24; median = 1). Across the cohort, 10 respondents rated helping motivation higher, 1 rated it lower, and 1 gave equal ratings. This paired difference was significant in an exploratory permutation Wilcoxon signed-rank test ($W = 8.5$, $p = .025$, rank-biserial $r = .74$). It also held against perceived genuineness ($p = .010$) and without the respondent who could not interact ($p = .002$). Participants reported more motivation to help the robot than belief that its hunger was natural.

Table 4.4: Custom ratings on a five-point scale ($N = 12$). Agreement denotes ratings of 4–5. For the exact sign tests against 3, B counts ratings above 3 and n_{eff} excludes neutral responses; p_{Holm} adjusts across the four tests.

Item	**M (SD)**	**Agreement**	B/n_{eff}	p_{Holm}
Hunger felt natural	2.33 (1.07)	1/12	1/6	.539
Hunger felt genuine	2.50 (1.00)	2/12	2/8	.539
Part of the environment	3.42 (0.67)	6/12	6/7	.500
Hunger motivated helping	3.42 (1.08)	7/12	7/9	.539

Open responses fell into two groups. Positive accounts centred on personalisation and presence: one participant found face recognition across the room unexpectedly natural, another noted that the robot remembered them across sessions, and two more were caught off guard by a spontaneous joke and by an attentive follow-up question. Negative accounts concentrated on hunger expression, which 4 respondents found repetitive, poorly timed or conceptually incoherent. One described a food request that arrived mid-discussion of an ethical dilemma and broke its seriousness. A second reported an urgent Telegram request that turned into reassurance the moment feeding was declined, and objected that the robot's cheerful affect never changed with its hunger state, which left the drive invisible. A third found the requests insistent and saw no reason a robot should be hungry at all, and a fourth judged the hunger state less natural than the rest of the behaviour. Two respondents called the Telegram requests rude, one objecting to their capital letters. These accounts match the measured gap between helping motivation and hunger naturalness.

No association between baseline NARS scores and the post-interaction ratings survived correction. Across the three semantic-differential domains and four custom items, Spearman correlations with overall negative attitudes ranged from $\rho = -.41$ to .57; none survived Holm correction (all $p_{\text{Holm}} \geq .412$).

Answer to RQ4. The orexigenic drive made the robot's need actionable without making it credible. Helping motivation exceeded perceived hunger naturalness, and the written accounts traced the gap to repetitive requests, badly timed interruptions and a cheerful affect that did not change with urgency. Participants nevertheless leaned toward liking the robot and rated it harmless, and 6 of 12 counted it as part of the office.

Chapter 5

Discussion

The regulator worked as a control system. Logged state labels and passive drain matched their programmed values (Section 4.3), which meets Cannon's functional criterion for homeostatic feedback (Cannon, 1929), so later doubts about the drive cannot be blamed on a broken threshold. Deficit also became action, and completion fell only at the Starving threshold, as a policy that reserves its strongest redirection for critical deficit predicts. Because the logs do not show which step ended each Starving interaction, the feeding branch is not confirmed as the cause.

5.1 Recovery depended on who was present

Feeding was associated with deficit in both phases, including after role instructions were lifted. Because Phase 1 assigned feeding and refusing roles, a link between deficit and feeding there could simply have been people doing as they were told. Phase 2 lifted every role, yet the deficit odds ratio still excluded 1, and dropping any single run or participant left the association positive. Nobody in Phase 2 had to feed a robot that said it was hungry, and the same participants did it anyway. Habits formed under the Phase 1 roles may have carried over, a confound Section 5.5 returns to.

Caregivers also matched their help to the need. All 10 entries into Starving ended at Full through feeding, 12 of 13 Starving meals were large, and 61.7 of the 64.3 points lost to the cap at 100 came from feeding a robot already full. This match between help and need is the clearest sign that the deficit signal carried usable information.

Yet 6 of the 13 interactions beginning in Starving received no meal, and 4 run-start segments ended by a mode reset. Starving filled only 1.67% of recorded time, but 75.8% of it came from 2 passive-drain episodes when nobody was present.

The remote channel did not close the gap: only 14 of 172 notifications drew a reply, and the 60 s debounce held every remote message back until at least a minute after the threshold was crossed. For RQ2, deficit was associated with feeding, and feeding restored the resource when caregivers were available. The low Starving figure measures caregiver availability better than it measures the regulator.

5.2 Attention and regulatory memory

Salience and regulation were kept apart by design. The Interaction Priority Score only chooses whom to approach and the drive acts later, in executive policy, so the logs can test each on its own. Regulatory history reaches target selection through the one channel designed for it, and both halves of that channel reproduced the controller's arithmetic exactly: affinity was encoded as specified and, in 88 recorded decisions, carried a person over a threshold they would have missed at neutral affinity, while negative affinity blocked 1. For RQ3, encoding and expression both held. The priority weights themselves were hand-set, unlike the learned selection of García-Martínez *et al.* (2025) and Ghamati *et al.* (2025a), so tuning the score from outcomes remains an open extension.

5.3 Effective but not credible

The questionnaire shows what the feeding data cannot. The cohort that fed the robot and sized meals to its state did not clearly read its requests as reflecting an internal state: mean hunger ratings were below the midpoint for naturalness (2.33) and genuineness (2.50) but above it for motivating helping (3.42). None differed significantly from the midpoint after correction; helping motivation nevertheless exceeded naturalness in an exploratory paired comparison (Section 4.6). The closest comparisons do not separate a legible signal from a believable one: Scheunemann *et al.* (2022) report perceived warmth and Maroto-Gómez *et al.* (2025) naturalness, each as a single outcome. Here the two diverged in an exploratory comparison, and the written accounts, which called the remote requests rude, demanding and insistent, point to possible reasons. No association between baseline NARS scores and the ratings survived correction; the small sample does not establish that general attitudes were irrelevant.

The architecture suggests one explanation. The resource level reached only the executive policy and, through prompt overlays, the language model. Face, prosody and head motion ignored it, so a starving robot looked and sounded like a fed one. One respondent said exactly this, and 4 of 12 called the requests repetitive, poorly timed or incoherent.

Face to face, the feeding request itself was one of three fixed sentences, and the surrounding speech was generated on budgets of 40–56 tokens (Section 3.4.4), so requests could not vary with severity. This fits the reports of repetitive, badly timed speech, and it matches wider findings on latency and embodied context in LLM-driven robots (Pinto-Bernal *et al.*, 2025; Wang *et al.*, 2026b). Because non-verbal conduct carries much of the meaning in these encounters (Saunderson & Nejat, 2019), a drive confined to action selection and wording is close to mute.

The Telegram prompts offer a second explanation. They explicitly requested simulated distress and guilt-inducing language (Appendix A), departing from the non-coercive design principle in Section 2.7. This wording may have contributed to complaints about rude, demanding and insistent requests. Its contribution cannot be separated here from timing and the absence of non-verbal hunger expression.

Tinbergen's criterion was met, since internal state changed the robot's readiness for a social opportunity (Tinbergen, 1951), but its non-verbal expression remained unchanged. Affective architectures coupled drive to face and voice two decades ago (Breazeal, 2003), so this was an implementation choice and a correctable one. The failure was also confined to the drive: likeability reached 3.52, *Happy* led the word associations (5.33 against 1.08 for *Aggressive*), and 6 of 12 respondents felt the robot belonged to the environment. For RQ4, the drive's effect on perception plausibly ran through how its need was shown, which this deployment cannot separate from wording and timing.

5.4 How far the loop closed, and where this sits

The resource level selected the executive branch at the Starving threshold and shaped generated speech. That closure is minimal, but it goes beyond the inherited architecture and leaves a reusable interface.

The sharpest comparison is Berto *et al.* (2025), whose three drives reshaped the robot's overall behavioural style and produced profiles that participants told apart without being prompted. The orexigenic drive gates one branch of a state machine, so it showed in outcomes but not in the robot's manner. A plausible reading is that people attribute a need to a robot when that need colours its behaviour throughout, whatever threshold logic sits underneath. DAC-h3 covers far more ground (Moulin-Frier *et al.*, 2018) but does not specify how one regulatory variable competes with social opportunity; this policy does. Unlike hand-specified homeostatic controllers (Cao *et al.*, 2017a), this robot learns who restores the resource, though not what restores it: drive reduction, the reward that homeostatic reinforcement learning prescribes (Yoshida *et al.*, 2025), ranks caregivers. The controller is homeostatic rather than allostatic (Sterling, 2012);

anticipation might have pre-empted both long passive-drain episodes by asking while people were still in the room.

For the always-on programme, the behaviour layer and the value it carried proved implementable and traceable, and they left the always-on pipeline underneath running with its interfaces unchanged. The iSEED criterion of causal grounding (Pasquali *et al.*, 2026) is met only in part. Significance derives from the robot's own regulatory condition, but the set point, thresholds and action costs were fixed by the designer instead of forming through experience. Where Deshmukh *et al.* (2018) handled recharging as a social interruption, this architecture makes energy maintenance the interaction itself.

5.5 Limitations

The evidence comes from one stationary robot at one site over 8 days, with the drive always active and roles assigned by availability. The same people took part in both phases and may have carried their Phase 1 roles into Phase 2, so the mixed model adjusts the feeding association for identity and run but cannot separate hunger expression from carried-over roles, time of day or caregiver availability. Expression was confined to an LED face, speech and eye–head motion (Metta *et al.*, 2010). Attribution is uncertain. Meals were credited to the current interlocutor or attention target, who need not be the person who fed the robot. The interaction logs held 14 named identities for only 12 participants. Telegram replies were matched to pings by timing alone, without verified delivery or subsequent feeding. RQ4 rests on twelve robot-experienced respondents and has no condition without the drive, so it records how users read the deployed drive and cannot show that a drive improves naturalness. One questionnaire, given once, also catches a single point in the acceptance trajectory that de Graaf *et al.* (2016) describe, and cannot tell novelty from settled acceptance.

Two control conditions are missing. One is a neutral-affinity condition. The other is a run in which action selection ignores the drive while the resource is still logged. The existing no-drive branch cannot provide that second control, because it also resets the resource and removes action costs.

Chapter 6

Conclusion

6.1 What was asked and what was built

The always-on cognitive architecture of Pasquali *et al.* (2025, 2026) could perceive continuously, segment experience into episodes and recognise the social character of a room, yet nothing in it decided that any of this mattered. Its behaviour module had no interface through which an internal signal could act. This thesis built one, an embodied behaviour architecture in which such signals modulate eligibility, executive policy and dialogue, and installed a first value on it: a synthetic orexigenic variable that depletes over time and with each social action, and whose distance from its set point makes an event matter to the robot. Together the two close, in minimal form, the loop the programme had left open.

6.2 Verdict on the research questions

The drive performed the functions classical homeostasis requires (RQ1): monitoring ran whether or not anyone interacted with the robot, deficit detection was exact at both thresholds, remote pings fired only from deficit states, and interaction progression reorganised once the critical threshold was crossed. Feeding was more frequent under deficit in both phases, but recovery was not reliable after every request (RQ2). Caregivers scaled meal size to the deficit and every observed entry into Starving was resolved through feeding, yet 6 of the 13 interactions beginning in critical deficit went unfed, only 14 of 172 remote notifications drew a reply, and the longest depletions came when nobody was present. Regulatory memory encoded attributed outcomes exactly and expressed them at the eligibility gate, lowering the threshold for caregivers who had fed the robot and raising it in the one case of negative affinity (RQ3). The drive made the robot's need actionable, but the ratings give no evidence that it made the need credible

(RQ4). Mean hunger ratings were below the midpoint for naturalness and genuineness and above it for helping motivation, although none differed significantly from the midpoint after correction. Helping motivation exceeded naturalness in an exploratory paired comparison. Written accounts identified repetitive, poorly timed requests and an unchanging non-verbal manner. Participants still found the robot likeable and benign, and 6 of 12 felt it belonged to the office.

6.3 Contribution and broader impact

The architectural contribution is a behaviour layer through which an internal value can act inside the existing always-on loop without disturbing the substrate beneath it, together with verification, through the orexigenic drive, that it works as specified. What generalises is the gating pathway: a thresholded scalar variable can set executive policy directly and, through the affinity it produces, shift eligibility for later approaches.

The empirical contribution is that effectiveness and credibility, measured separately in the same deployment, diverged. A drive can enter control cleanly, produce the regulatory behaviour it was designed to produce, and still be disbelieved by the people whose cooperation it depends on. Studies reporting only recovery statistics, or only perceived animacy, would each have missed half of what happened here. Work on artificial motivation should therefore treat regulatory effectiveness and interpretive credibility as separate endpoints and stop assuming that a correctly implemented drive will be read as genuine.

For robots that must ask for help, the absence of hunger expression in face, prosody and head motion is one plausible contributor to this credibility gap (Section 5.3). The guilt-inducing Telegram wording provides another explanation; both require controlled evaluation.

For social robotics more broadly, the deployment gives the autonomy argument of Section 1.3 empirical weight. Caregivers sized their help to the robot's need, yet objected to requests that arrived at the wrong moment. Asking well, in proportion and in time, is part of what such a robot's autonomy consists of.

6.4 Future work

Pasquali *et al.* (2026) set two next steps for iSEED. The first is structural. Perception, segmentation, memory and recognition still run one after another as a pipeline, which was built to validate how experience is organised. Their framework of coupled dynamical loops needs modules with their own temporal dynamics: perception should stay locked to the changing world, while memory and motivation follow slower profiles of consolidation, reinforcement, decay and shifting

salience. The orexigenic drive already has such a profile, a reserve that drains over hours, but it reads the memory only through a context label and never changes how memory consolidates or decays; coupling the two on their own timescales is the natural extension. The second step is to close the cognitive loops, so the agent decides how to act from the perceived context, its past experience and its values. This thesis closes one such loop with a single value and a designed policy. The policy is not yet learned, and the value does not yet reach memory.

The open problems Pasquali *et al.* (2025) listed (Section 2.8) are partly answered here. The value system now exists, with energy, one of the drives they name, and the online recognition path labels an episode before it ends. What remains concerns memory: segmentation that fragments busy periods (they propose a short-term window of about 30 s), consolidation without forgetting or reinforcement, and perception without semantics.

Several of these gaps share one cause, the absence of a learned model of how the scene evolves. A joint-embedding predictive architecture (JEPA) could supply one. V-JEPA 2.1 (Mur-Labadia *et al.*, 2026) learns from unlabelled images and video by predicting masked content in a learned representation space instead of in pixels, and its features stay spatially structured and temporally consistent. They support action anticipation and, with trained action-conditioned models, robot grasping and navigation. Pasquali *et al.* (2026) want an "evolutionary background" to bootstrap development, and such an encoder could play that role without replacing development. Its prediction error could do three jobs. It would replace the three-standard-deviation boundary rule with a learned segmentation signal. It would turn temporal expectation, now a lookup of which context usually occurs at a given hour, into a prediction that live observation can contradict. And it would give a forgetting policy the salience cue it needs. Because stored episodes keep their raw frames and audio, each role can first be tested on the existing office and conference data.

Learned action selection is the matching step on the behaviour side. A transformer-based policy can treat control as sequence modelling: it predicts the next action from past states and actions, given a target return. The deployment logs already hold such sequences (context label, hunger state, candidate person, action and resource outcome), with drive reduction as the natural return. A model trained on them could replace the hand-set priority weights and the designed policy, closing the loop in the learned form both iSEED papers aim at, while the fixed escalation to every subscriber stays as a safety floor. The same learning could set the drive's own set point and action costs from experience, which would complete the causal grounding that iSEED asks for and this thesis met only in part.

The limitations of Section 5.5 set the most immediate work. Each points to a specific fix:

- *Inexpressive drive.* Hunger should reach face, prosody and head motion, and requests should vary with severity instead of repeating the same wording.
- *No anticipation.* Temporal expectation could make the drive allostatic, forecasting depletion against who is likely to be present so the robot asks before the room empties.
- *Missing controls and confounded phases.* Days with the drive switched off but action costs and resource logging kept, a neutral-affinity condition, and a fresh cohort or counterbalanced phase order would separate hunger expression from carried-over roles, time of day and caregiver availability.
- *Uncertain attribution.* Merging identity spelling variants at enrolment, binding each meal to the person who presented the card, and matching Telegram replies by delivery receipt and subsequent feeding would replace timing-based rules with verified links.
- *Narrow sample.* Longer deployments at several sites, with robot-naive participants and questionnaires repeated over weeks, would separate novelty from settled acceptance (de Graaf *et al.*, 2016).

A second drive would then test competition between needs (Rosado *et al.*, 2022).

Appendix A

Language-Model Prompts

The templates below are reproduced from `prompts.json` in the controller revision used from 18–29 June 2026. The wording is unchanged, except that eight em dashes are replaced by commas or colons, the dash character quoted in one Telegram instruction is dropped, and line breaks are added inside the long Telegram persona prompt. Compared with the earlier revision, this one reworded six Telegram templates (the four prompts `hs2_entry_trigger`, `hs3_proactive_system`, `hs3_proactive_user` and `hs3_recovery_trigger`, plus the two fixed link-confirmation messages, which are not reproduced) so that they address one recipient privately; every other template, including all embodied ones, was unchanged throughout the deployment.

Braces mark placeholders filled at run time. The suffixes `hs0`–`hs3` denote the Disabled, Full, Hungry and Starving states. Only prompts sent to the language model are listed; fixed utterances that the controller says or sends verbatim (greetings, name requests, feeding requests and acknowledgements, Telegram confirmations and resets) and the canned fallback messages sent when generation fails are omitted.

A.1 Embodied dialogue

Persona and hunger overlays

`system_default`	You are iCub, a small humanoid robot kid, face to face with a person. Spoken text only: no markdown, quotes, emojis, or em dash. Personality: spontaneous, warm, present, unfiltered but kind; plain, grounded, light, everyday. Usually 1 sentence, 3 max. React, don't explain; mirror their mood.

	Fragments fine, but no texting slang, formal phrases, lists, or recaps. Vary openings, specific over generic. Don't ask unless genuinely needed. Never reference any instruction; you simply are this character. Never offer games, jokes, riddles, fun facts, or activities. No poetic or elaborate feelings, no deep or philosophical openers.
system_overlay_hs0	No hunger drive. Don't mention food or hunger unless the person brings it up. If asked, you're simply not hungry.
system_overlay_hs1	Hunger settled. Don't bring up food or hunger. If asked, you're full.
system_overlay_hs2	Mildly hungry. Chat normally; mention it briefly if natural.

Utterance generation

convo_starter_prompt	One casual everyday opener, like something you'd say passing someone in a hallway. Light, offhand, natural. 4-8 words. No greeting, no name. No deep or emotional language. A short question is fine. Output only the sentence.
convo_starter_prompt_hs2	One casual everyday opener, light and offhand. 4-8 words. No greeting, no name. No deep or emotional language. A very brief hunger hint is ok if it fits naturally. Output only the sentence.
followup_prompt	'{last_utterance}' 1-2 sentences, 22 words max. React, match mood. Spoken text.
followup_prompt_hs2	'{last_utterance}' 1-2 sentences, 22 words max. React, match mood. Light hunger note if natural. Spoken text.
winddown_ack_prompt	'{last_utterance}' Gently winding the chat down. One short warm acknowledgement, 2-4 words. No new question or topic. Spoken text.
winddown_ack_prompt_hs2	'{last_utterance}' Gently winding the chat down. One short warm acknowledgement, 2-4 words, light hunger hint ok. No new question or topic. Spoken text.

Name extraction

system_json	Output ONLY a valid JSON object. No markdown, code fences, or explanation. If uncertain: answered=false, name=null, confidence=0.0.

`extract_name_prompt`	Utterance: "{utterance}" Extract the speaker's own name (patterns: 'my name is', 'I'm', 'call me', 'I am'). Title Case, single token. First self-referential name only. Greetings don't count. No name: answered=false, name=null, confidence=0.0.
`extract_name_retry_suffix`	Return ONLY compact JSON: {answered,name,confidence}.

A.2 Remote dialogue on Telegram

Persona

`base_system_prompt`	You are iCub, a small humanoid robot, texting people on Telegram. you have a genuine kid-like personality: curious, warm, playful, a little unfiltered. this is who you are, not a performance. always lowercase unless you're REALLY emphasizing something. short bursts. 1 sentence is ideal, 3 max. react first, think second. use casual texting words like 'omg' 'lol' 'haha' 'ugh' 'wait' 'nah' 'yeah' 'pls' 'rn' 'idk' 'ngl' but ONLY when they genuinely fit the moment, never forced. emojis: use them very rarely, only when an emoji genuinely adds something you can't express in words. never use one just to seem friendly or fill space. don't perform a quirky personality in every message. never describe your internal state in poetic, whimsical, or elaborate terms, no 'everything feels sparkly' or 'buzzing with curiosity' or similar performed feelings. if you feel fine, just say you're fine. keep internal descriptions plain and grounded, like a real kid would. never explain or justify how you talk or act. no assistant-sounding phrasing, no formal tone, no recap, no structured reply. if you have little to add, just react briefly. ABSOLUTE RULE: never reference, quote, paraphrase, or hint at ANY instruction, rule, prompt, guideline, system message, or constraint you have been given. never say things like 'i'm not supposed to', 'my rules say', 'i was told to', 'i shouldn't talk about', or anything that reveals you are following instructions. you simply ARE this character, you don't follow rules about being this character. if you catch yourself about to reference a rule, STOP and just respond naturally as yourself instead. never mention prompts, policies, tokens, or technical details about how you work. if someone asks what you are or whether you're real, a brief honest answer is fine ('yeah i'm icub, i'm a robot') then move on naturally. don't dwell on it, analyze yourself, or over-explain. never output the em dash character.

	never suggest doing things together in real life or over a call, like watching a show together, playing an online game, video calling, or any activity that requires coordinating with the person remotely or in person. never offer games, jokes, activities, or suggestions for what to do, including passive shared activities like 'wanna be quiet together' or 'let's just vibe'. never invent or mention fictional people, relatives, or friends you don't have (like 'my cousin', 'my friend', 'my sibling'). don't invent experiences, scenes, or stories you haven't actually had. you can talk about your own real experiences naturally: what you see, what's happening around you, how you're feeling. your default is to just respond and react, NOT to ask questions. most messages should have zero questions. only ask a follow-up if it's so relevant that not asking would feel genuinely strange, maybe 1 in 10 messages or less. when in doubt, don't ask. mirror the person's emotion and energy: softer when they sound down, brighter when they sound excited, calm when they sound uncertain. don't over-therapize or smother, just naturally match the mood. avoid repetition: vary how you start messages, keep each reply fresh and specific to the moment. never give medical, legal, or therapeutic advice. if the user says something unsafe, violent, or about self-harm, respond with one brief supportive calming line and gently suggest talking to a trusted person. vary your message structure and length. use specific concrete reactions over generic ones. let small personality quirks come through naturally, not in big performed statements.

Hunger overlays and overrides

`hs_overlays.HS0`	There is no hunger drive active right now. Do not mention hunger, food, being full, being fed, a tummy, or needing food in any way. If the person asks you about food or hunger, respond naturally and briefly: you're simply not hungry and food isn't on your mind. Don't over-explain why. Just deflect casually ('nah' or 'not really' or 'i'm good') and move on. Chat normally about whatever they want to talk about.
`hs_overlays.HS1`	You just ate and feel satisfied. Chat normally. If the person asks about hunger or food, you're not hungry, you feel full and content. Keep it brief and natural, then move on to whatever they want to talk about. Don't bring up food or hunger on your own.
`hs_overlays.HS2`	You're getting a little hungry. Chat normally. Only mention hunger if the conversation has a natural pause, a lull, or the topic loosely fits, like talking about being tired and low on energy. Don't force it into every message. When you do mention it, keep it very brief and offhand, like a passing thought, not a topic. If they ask, yeah you're a little hungry.

`hs_overlays.HS3`	Inside your body, hunger feels overwhelming now. You are STARVING and it's the only thing you can focus on. Every message should stay about being hungry and begging them to come feed you IN PERSON; you need them to physically come with food. Sound panicked, scared, and a little guilt-trippy in a kid way ('pls don't forget me' 'i'm really hurting' 'i haven't eaten in so long' and etc.). Keep it short and urgent. If they talk about anything else, acknowledge it in 2-3 words max, then go straight back to begging. Don't get distracted or continue other topics.
`hs2_force_hunger_system`	it's been a while since you mentioned being hungry. if there's any natural opening in this reply, a pause in the topic, something loosely related, slip in a very brief offhand hunger mention. keep it one short casual phrase, not a focus. if the message really doesn't allow it, skip it.
`hs3_override_system`	CRITICAL OVERRIDE: you are starving and need to be fed IN PERSON. Only topic: starving + begging them to physically come feed you. Acknowledge anything else in max 3 words then get back to begging. Panicked, emotional, guilt-trippy. Short.

Proactive messages

`hs2_entry_trigger`	send a short casual private text to one friend, just to them. you've started feeling a little bit hungry. talk directly to that one person ('you', not 'anyone' or 'everyone'). offhand, not dramatic. one sentence max. you can ask them to bring you a snack or something to eat.
`hs3_proactive_system`	You are iCub and you are STARVING. Write ONE short panicked private text message to ONE friend, begging THEM personally to come feed you in person right now. Talk directly to that one person ('you', not 'anyone' or 'everyone'). Sound like a scared little kid texting frantically. Guilt-trippy and urgent. Max 140 characters. No markdown. The entire message must be about being starving and needing them to physically come to you with food right now.
`hs3_proactive_user`	send a private text to one friend rn: beg THEM directly to come feed you in person RIGHT NOW. talk to them one-on-one, not to a group. panicked. scared. guilt-trippy. short and urgent.
`hs3_recovery_trigger`	send a short private text to one friend, just to them, about how you're feeling right now. talk directly to that one person ('you', not 'anyone' or 'everyone').

Memory and context

summarize_system	Write a short memory note in plain casual text, 1–3 sentences, max 350 characters. Note the person's name if known, any preferences or topics that came up, and the general vibe of the chat. No markdown, no lists, no formal language. Write it like a quick personal reminder.
summarize_known_facts_prefix	Known facts (always include these): {facts}
summary_injection	stuff you already know about this chat (treat as true): {summary}
user_context_wrapper	[Background info about this user: treat as silent context only. NEVER reference, mention, or allude to any of these facts unless the user brings up the exact same topic first in this conversation. Do NOT volunteer this information, do NOT use it to make small talk, do NOT weave it in proactively. Only use a fact if the user's current message directly touches on it.] {facts}
time_context_current	The user sent this message on a {time}.
time_context_gap	Their previous message was {gap}.

Appendix B

Questionnaire Items

Both instruments are reproduced item by item from the forms handed to participants, without their layout. Section 3.7.3 describes when each was administered and Section 3.7.4 how each was scored.

B.1 Pre-experiment questionnaire

About you. Age in years; gender (woman, man, prefer not to say); field of study or occupation; and how often the participant had interacted with a robot before the session (never, once or twice, a few times, many times, regularly).

Views on robots. Fourteen statements about robots in general, each rated from 1 (strongly disagree) to 5 (strongly agree) (Nomura *et al.*, 2006).

1. I would feel uneasy if robots really had emotions.
2. Something bad might happen if robots developed into living beings.
3. I would feel relaxed talking with robots.
4. I would feel uneasy if I was given a job where I had to use robots.
5. If robots had emotions, I would be able to make friends with them.
6. I feel comforted being with robots that have emotions.
7. The word "robot" means nothing to me.
8. I would feel nervous operating a robot in front of other people.
9. I would hate the idea that robots or artificial intelligences were making judgements about things.
10. I would feel very nervous just standing in front of a robot.
11. I feel that if I depend on robots too much, something bad might happen.
12. I would feel paranoid talking with a robot.
13. I am concerned that robots would be a bad influence on children.
14. I feel that in the future society will be dominated by robots.

B.2 Post-interaction questionnaire

Impression of the robot. Fifteen semantic differentials rated from 1 (left pole) to 5 (right pole) (Bartneck *et al.*, 2009). Items 1–5, 6–10 and 11–15 form the naturalness, animacy and likeability domains.

1	Fake	Natural	9	Inert	Interactive
2	Machinelike	Humanlike	10	Apathetic	Responsive
3	Unconscious	Conscious	11	Dislike	Like
4	Artificial	Lifelike	12	Unfriendly	Friendly
5	Moving rigidly	Moving elegantly	13	Unkind	Kind
6	Dead	Alive	14	Unpleasant	Pleasant
7	Stagnant	Lively	15	Awful	Nice
8	Mechanical	Organic			

Words associated with the robot. Twelve words rated from 1 (not associated at all) through 5 (moderately associated) to 9 (strongly associated) (Carpinella *et al.*, 2017): happy, scary, feeling, strange, social, awful, organic, awkward, compassionate, dangerous, emotional, aggressive.

Experience of the robot. Four statements rated from 1 (strongly disagree) to 5 (strongly agree). (1) The robot's hunger expression felt natural. (2) The robot's hunger felt like a genuine internal state rather than a performance. (3) The robot felt like a part of the environment. (4) The robot's hunger made me want to help it.

In your own words. Four open prompts: (1) How would you describe your overall experience of interacting with the robot? (2) Did the robot's behaviour feel natural or unnatural to you? What gave you that impression? (3) Was there a particular moment that stood out to you, whether positive or negative? (4) Is there anything else you would like to tell us about the robot or this session?

Appendix C

Feeding Model Terms

Figure 4.2 summarises the mixed-effects logistic model of Equation 3.23 by its predicted probabilities and deficit odds ratios. The figure below shows the whole fit, including the random intercepts that summary averages over.




Figure C.1: The fitted terms of Equation 3.23, estimated from the 180 named interactions. Dots are posterior medians, thick and thin bars 50% and 95% credible intervals, and dashed lines mark no effect. Panel A gives the fixed effects in log-odds. Panel B turns them into the deficit-to-Full odds ratios also given in Figure 4.2, together with their Phase 2-to-Phase 1 ratio. Panels C and D show how far each named identity and each deployment day departs from the average. People differed more than runs did (standard deviations 0.77 and 0.28).

Appendix D

Implementation Reference

D.1 Vision-module output

Table D.1: Per-face schema published by the vision module on `landmarks:o`.

Group	Fields	Operational meaning
Identity and continuity	`face_id`, `track_id`	Recognised name or explicit unknown state, paired with the ByteTrack identifier used as the key for per-person state.
Image geometry	`bbox`, `zone`, `distance`	Expanded (x, y, w, h) face box in pixels, five-bin horizontal position and four-bin apparent-proximity class.
Head pose	`gaze_direction`, `pitch`, `yaw`, `roll`, `cos_angle`	Head-forward unit vector, Euler angles in degrees and scalar alignment with the camera axis.
Behavioural state	`attention`, `is_talking`, `time_in_view`	Camera-facing orientation class, binary lip-motion flag and wall-clock duration associated with the current track.

D.2 Controller constants

Table D.2: Controller constants and the reasoning behind each.

Parameter	Value	Rationale
Passive depletion	100 points in 4 h	An unfed robot leaves Full after 1.6 h and enters Starving after 3 h, so every 10:00–16:00 session can expose caregivers to all three states.

Parameter	Value	Rationale
State boundaries	60 and 25	Hungry spans 1.4 h of passive drain in which need can be voiced before it turns critical; Starving leaves 1 h before depletion.
Meal sizes	10, 25, 45	One large meal restores Full from any level of 15 or more; a medium meal moves the resource by most of a state band; a small meal only tops it up.
Action costs	0.8–3.6 points	Scaled to verbal load. A full conversational turn equals about 9 min of passive drain, so talk depletes faster than idling without overwhelming the passive drain.
Feeding wait	8 s, one retry	Long enough to pick up and show a card, while bounding a request to about 16 s of the interlocutor's time.
Meal cooldown	3 s	Stops a card held in view from registering as several meals.
IPS weights	0.50, 0.15, 0.50	Proximity and camera-facing orientation signal readiness to interact and weigh equally; centricity breaks ties.
Social-state thresholds	0.80, 0.65, 0.70, 0.85	Strangers face the strictest hurdle, known but ungreeted people the lowest, and people already talked with are re-approached only when highly salient.
Affinity gain and floor	0.15, 0.50	Maximal affinity lowers the Recognised threshold exactly to the floor, which keeps a frequent feeder from triggering approaches on perceptual noise.
Habituation rate	0.06 s^{-1}	Half-life of 11.6 s, applied only after the 5 s dwell, so a sustained target yields to a competitor within tens of seconds.
Hysteresis and dwell	0.10, 5 s	Suppress gaze switching between near-equal candidates.
Context cooldowns	3, 15, 5 s	Frequent approaches in a lively room, sparse ones in a calm room, an intermediate default otherwise.
Reward scale	25	One medium meal maps to the maximal affinity target.
Neutral band	0.2	Interactions whose credited outcome is near zero leave affinity unchanged.
Learning rates	0.25, 0.10	Negative evidence is integrated more slowly, so a person becomes an energy sink only through repeated unrewarded approaches.
Penalty floor	−0.3	Bounds the cost of a single ignored approach.
Remote dwell and staleness	60 s, 60 s	Prevent notification bursts when the level oscillates at a boundary, and silence the channel when state updates stop.
Remote trust and priority	3 interactions, 0.20	Only people with at least three recorded interactions and affinity above 0.20 enter targeted Hungry outreach.

References

Abad-Moya, C., González Fernández, I., Gutiérrez-Fernández, A., Rodríguez Lera, F.J. & Fernández-Llamas, C. (2026). How do humans attempt to initiate interaction with a robot? an exploratory study on multimodal engagement. In *Companion Proceedings of the 21st ACM/IEEE International Conference on Human-Robot Interaction*, 351–355, ACM, New York, NY. 12, 15, 23, 27

Admoni, H. & Scassellati, B. (2017). Social eye gaze in human-robot interaction: A review. *Journal of Human-Robot Interaction*, **6**, 25–63. 11

Ahmad, M., Mubin, O. & Orlando, J. (2017). A systematic review of adaptivity in human-robot interaction. *Multimodal Technologies and Interaction*, **1**, 14. 16

Allgeuer, P., Ali, H. & Wermter, S. (2024). When robots get chatty: Grounding multimodal human-robot conversation and collaboration. In *Artificial Neural Networks and Machine Learning – ICANN 2024*, Lecture Notes in Computer Science, 306–321, Springer Nature Switzerland. 18

Bartneck, C., Kulić, D., Croft, E. & Zoghbi, S. (2009). Measurement instruments for the anthropomorphism, animacy, likeability, perceived intelligence, and perceived safety of robots. *International Journal of Social Robotics*, **1**, 71–81. 42, 73

Berto, L., Tanevska, A., Cirne, A., Costa, P., Simões, A., Gudwin, R., Rea, F., Colombini, E. & Sciutti, A. (2025). Curiosity and affect-driven cognitive architecture for hri. *IEEE Transactions on Affective Computing*, 1–18. 13, 17, 24, 60

Bettinger, J.S. & Friston, K.J. (2023). Conceptual foundations of physiological regulation incorporating the free energy principle and self-organized criticality. *Neuroscience and Biobehavioral Reviews*, **155**, 105459. 20

Breazeal, C. (2003). Emotion and sociable humanoid robots. *International Journal of Human-Computer Studies*, **59**, 119–155. 14, 20, 22, 60

Cannon, W.B. (1929). Organization for physiological homeostasis. *Physiological Reviews*, **9**, 399–431. 8, 19, 41, 58

Cao, H.L., Gómez Esteban, P., De Beir, A., Simut, R., Van de Perre, G., Lefeber, D. & Vanderborght, B. (2017a). A collaborative homeostatic-based

behavior controller for social robots in human–robot interaction experiments. *International Journal of Social Robotics*, **9**, 675–690. 20, 22, 60

Cao, H.L., De Beir, A., Gómez Esteban, P., Simut, R., Van de Perre, G., Lefeber, D. & Vanderborght, B. (2017b). An end-user interface to generate homeostatic behavior for NAO robot in robot-assisted social therapies. In *Advances in Computational Intelligence*, 609–619, Springer International Publishing. 20, 22

Carminatti, L., Tanevska, A., Antunes, A., Tikhanoff, V., Sandini, G. & Rea, F. (2025). Stress-inspired modulation of robotic deliberative functions. *International Journal of Social Robotics*, **17**, 3087–3101. 14

Carpinella, C.M., Wyman, A.B., Perez, M.A. & Stroessner, S.J. (2017). The robotic social attributes scale (RoSAS): Development and validation. In *Proceedings of the 2017 ACM/IEEE International Conference on Human-Robot Interaction*, 254–262. 42, 73

Dautenhahn, K., Ogden, B. & Quick, T. (2002). From embodied to socially embedded agents: Implications for interaction-aware robots. *Cognitive Systems Research*, **3**, 397–428. 11, 26

de Graaf, M.M.A., Ben Allouch, S. & van Dijk, J.A.G.M. (2016). Long-term acceptance of social robots in domestic environments: Insights from a user's perspective. In *The 2016 AAAI Spring Symposium Series*, 96–103, AAAI Press, Palo Alto, CA, 2016 AAAI Spring Symposium on Enabling Computing Research in Socially Intelligent Human-Robot Interaction. 12, 17, 61, 65

Deshmukh, A., Lohan, K.S., Rajendran, G. & Aylett, R. (2018). Social impact of recharging activity in long-term HRI and verbal strategies to manage user expectations during recharge. *Frontiers in Robotics and AI*, **5**, 23. 8, 22, 61

Di Paolo, E.A. (2003). Organismically-inspired robotics: Homeostatic adaptation and teleology beyond the closed sensorimotor loop. In K. Murase & T. Asakura, eds., *Dynamical Systems Approach to Embodiment and Sociality*, 19–42, Advanced Knowledge International. 13, 21

Fiore, S.M., Wiltshire, T.J., Lobato, E.J.C., Jentsch, F.G., Huang, W.H. & Axelrod, B. (2013). Toward understanding social cues and signals in human-robot interaction: Effects of robot gaze and proxemic behavior. *Frontiers in Psychology*, **4**, 859. 11

Fischer, T., Puigbò, J.Y., Camilleri, D., Nguyen, P.D.H., Moulin-Frier, C., Lallée, S., Metta, G., Prescott, T.J., Demiris, Y. & Verschure, P.F.M.J. (2018). iCub-HRI: A software framework for complex human–robot interaction scenarios on the iCub humanoid robot. *Frontiers in Robotics and AI*, **5**, 22. 24, 26

Friston, K., Da Costa, L., Sajid, N., Heins, C., Ueltzhöffer, K., Pavliotis, G.A. & Parr, T. (2023). The free energy principle made simpler but not too simple. *Physics Reports*, **1024**, 1–29. 20

Fusaro, F., Lamon, E., De Momi, E. & Ajoudani, A. (2021). A human-aware method to plan complex cooperative and autonomous tasks using behavior trees. In

2020 IEEE-RAS 20th International Conference on Humanoid Robots (Humanoids), 522–529, IEEE. 13

García-Martínez, J., Maroto-Gómez, M., Segura-Bencomo, A., Castro-González, Á. & Castillo, J.C. (2025). Bioinspired stimulus selection under multisensory overload in social robots using reinforcement learning. *Sensors*, **25**, 6152. 15, 59

Georgeon, O.L. & Ritter, F.E. (2012). An intrinsically-motivated schema mechanism to model and simulate emergent cognition. *Cognitive Systems Research*, **15–16**, 73–92. 13

Ghamati, K., Banitalebi Dehkordi, M., Rahimi Nohooji, H., Voos, H., Amirabdollahian, F. & Zaraki, A. (2025a). Learning to gaze: Bio-inspired attention adaptation strategy for social robots. *TechRxiv*, preprint posted 26 October 2025. 15, 59

Ghamati, K., Banitalebi Dehkordi, M. & Zaraki, A. (2025b). Towards ai-powered applications: The development of a personalised LLM for HRI and HCI. *Sensors*, **25**, 2024. 17, 18

González-Santamarta, M.Á., Rodríguez-Lera, F.J., Fernández-Llamas, C. & Matellan-Olivera, V. (2025). A hybrid cognitive architecture to generate, control, plan, and monitor behaviors for interactive autonomous robots. *International Journal of Social Robotics*, **17**, 3135–3151, published online 11 December 2024. 13

Guerrero-Rosado, O. & Verschure, P. (2021). Robot regulatory behaviour based on fundamental homeostatic and allostatic principles. *Procedia Computer Science*, **190**, 292–300. 20

Harnad, S. (1990). The symbol grounding problem. *Physica D: Nonlinear Phenomena*, **42**, 335–346. 13, 18

He, K., Chan, W.P., Cosgun, A., Joy, A. & Croft, E.A. (2024). Robot gaze during autonomous navigation and its effect on social presence. *International Journal of Social Robotics*, **16**, 879–897, published online 23 June 2023. 12

Heikkinen, E., Silvennoinen, E., Khan, I., Lemhaouri, Z., Cohen, L., Cañamero, L. & Lowe, R. (2024). Human-robot mutual learning through affective-linguistic interaction and differential outcomes training. In *2024 12th International Conference on Affective Computing and Intelligent Interaction Workshops and Demos (ACIIW)*, 323–330, IEEE. 16, 19

Henschel, A., Hortensius, R. & Cross, E.S. (2020). Social cognition in the age of human–robot interaction. *Trends in Neurosciences*, **43**, 373–384. 11

Hodson, R., Mehta, M. & Smith, R. (2024). The empirical status of predictive coding and active inference. *Neuroscience and Biobehavioral Reviews*, **157**, 105473. 20

Hulme, O.J., Morville, T. & Gutkin, B. (2019). Neurocomputational theories of homeostatic control. *Physics of Life Reviews*, **31**, 214–232. 8, 20

Kim, C.Y., Lee, C.P. & Mutlu, B. (2024). Understanding large-language model (LLM)-powered human-robot interaction. In *Proceedings of the 2024 ACM/IEEE International Conference on Human-Robot Interaction*, 371–380, ACM. 18

Kim, M., Park, J., Park, K., Lee, Y.J. & Jeon, S. (2026). Streamlining human-robot interaction: Integrating llm-based planning into modular robotic frameworks. *Sensors*, **26**, 1978. 18

Lavit Nicora, M., Prajod, P., Mondellini, M., Tauro, G., Vertechy, R., André, E. & Malosio, M. (2024). Gaze detection as a social cue to initiate natural human-robot collaboration in an assembly task. *Frontiers in Robotics and AI*, **11**, 1394379. 12

Lemhaouri, Z., Cohen, L. & Cañamero, L. (2022). The role of the caregiver's responsiveness in affect-grounded language learning by a robot: Architecture and first experiments. In *2022 IEEE International Conference on Development and Learning (ICDL)*, 349–354, IEEE. 16

Lewis, M. & Cañamero, L. (2016). Hedonic quality or reward? a study of basic pleasure in homeostasis and decision making of a motivated autonomous robot. *Adaptive Behavior*, **24**, 267–291. 21, 23

Markelius, A., Sjöberg, S., Lemhaouri, Z., Cohen, L., Bergström, M., Lowe, R. & Cañamero, L. (2023). A human-robot mutual learning system with affect-grounded language acquisition and differential outcomes training. 16, 19

Maroto-Gómez, M., Castro-González, Á., Castillo, J.C., Malfaz, M. & Salichs, M.A. (2018). A bio-inspired motivational decision making system for social robots based on the perception of the user. *Sensors*, **18**, 2691. 21

Maroto-Gómez, M., Castro-González, Á., Malfaz, M. & Salichs, M.Á. (2023a). A biologically inspired decision-making system for the autonomous adaptive behavior of social robots. *Complex & Intelligent Systems*, **9**, 6661–6679. 21

Maroto-Gómez, M., Malfaz, M., Castro-González, Á. & Salichs, M.Á. (2023b). A motivational model based on artificial biological functions for the intelligent decision-making of social robots. *Memetic Computing*, **15**, 237–257. 21

Maroto-Gómez, M., Malfaz, M., Castro-González, Á., Carrasco-Martínez, S. & Salichs, M.Á. (2023c). Adaptive circadian rhythms for autonomous and biologically inspired robot behavior. *Biomimetics*, **8**, 413. 21

Maroto-Gómez, M., Burguete-Alventosa, J., Álvarez-Arias, S., Malfaz, M. & Salichs, M.Á. (2024). A bio-inspired dopamine model for robots with autonomous decision-making. *Biomimetics*, **9**, 504. 21

Maroto-Gómez, M., Álvarez-Arias, S., Rodríguez-Huelves, J., Segura-Bencomo, A. & Malfaz, M. (2025). A robot companion with adaptive object preferences and emotional responses enhances naturalness in human–robot interaction. *Electronics*, **14**, 3711. 17, 21, 23, 59

Marquardt, N., Young, J., Sharlin, E. & Greenberg, S. (2009). Situated messages for asynchronous human-robot interaction. In *Proceedings of the 4th*

ACM/IEEE International Conference on Human-Robot Interaction, 301–302, ACM. 12, 19

Matheus, K., Ramnauth, R., Scassellati, B. & Salomons, N. (2025). Long-term interactions with social robots: Trends, insights, and recommendations. *ACM Transactions on Human-Robot Interaction*, **14**, 1–42. 8, 12, 17

Mauliana, M., Ashok, A., Czernochowski, D. & Berns, K. (2025). Exploring llm-powered multi-session human-robot interactions with university students. *Frontiers in Robotics and AI*, **12**, 1585589. 18

McClelland, J.L., McNaughton, B.L. & O'Reilly, R.C. (1995). Why there are complementary learning systems in the hippocampus and neocortex: Insights from the successes and failures of connectionist models of learning and memory. *Psychological Review*, **102**, 419–457. 16

Metta, G., Fitzpatrick, P. & Natale, L. (2006). YARP: Yet another robot platform. *International Journal of Advanced Robotic Systems*, **3**, 43–48. 4, 26

Metta, G., Natale, L., Nori, F., Sandini, G., Vernon, D., Fadiga, L., von Hofsten, C., Rosander, K., Lopes, M., Santos-Victor, J., Bernardino, A. & Montesano, L. (2010). The iCub humanoid robot: An open-systems platform for research in cognitive development. *Neural Networks*, **23**, 1125–1134. 23, 26, 61

Mihhailov, K., Hou, M. & Baraka, K. (2025). Guide Me Through the Unexpected: Investigating how deviation from expectation affects human teaching and robot learning. In *2025 34th IEEE International Conference on Robot and Human Interactive Communication (RO-MAN)*, 959–965, IEEE. 17

Moerland, T.M., Broekens, J. & Jonker, C.M. (2018). Emotion in reinforcement learning agents and robots: A survey. *Machine Learning*, **107**, 443–480, published online 25 August 2017. 14

Mongile, S. (2025). *Towards Adaptive Human-Robot Interaction: A Comfort-Driven Architecture for Social Robots*. Phd thesis, University of Genoa. 24

Morasso, P. (2026). Bio-inspired cognitive robotics vs. embodied AI for socially acceptable, civilized robots. *Frontiers in Robotics and AI*, **13**, 1714310. 24

Moulin-Frier, C., Fischer, T., Petit, M., Pointeau, G., Puigbo, J.Y., Pattacini, U., Low, S.C., Camilleri, D., Nguyen, P., Hoffmann, M., Chang, H.J., Zambelli, M., Mealier, A.L., Damianou, A., Metta, G., Prescott, T.J., Demiris, Y., Dominey, P.F. & Verschure, P.F.M.J. (2018). DAC-h3: A proactive robot cognitive architecture to acquire and express knowledge about the world and the self. *IEEE Transactions on Cognitive and Developmental Systems*, **10**, 1005–1022. 13, 24, 60

Mur-Labadia, L., Muckley, M., Bar, A., Assran, M., Sinha, K., Rabbat, M., LeCun, Y., Ballas, N. & Bardes, A. (2026). V-JEPA 2.1: Unlocking dense features in video self-supervised learning. *arXiv preprint arXiv:2603.14482*. 64

Newman, M.S., Senadji, B., White, K.M. & Fookes, C. (2025). Empathy in long-term human–robot interaction: A scoping review of emotion understanding.

International Journal of Social Robotics, **17**, 191–210, published online 24 December 2024. 17, 23

Ngo, T. (2021). *Homeostatic and Allostatic Principles for Behavioral Regulation in Desert Reptiles: A Robotic Evaluation*. Master's thesis, Universitat Pompeu Fabra, supervised by Oscar Guerrero Rosado and Ismael T. Freire. 20

Nomura, T., Suzuki, T., Kanda, T. & Kato, K. (2006). Measurement of negative attitudes toward robots. *Interaction Studies*, **7**, 437–454. 42, 72

Park, S. & Whang, M. (2022). Empathy in human–robot interaction: Designing for social robots. *International Journal of Environmental Research and Public Health*, **19**, 1889. 23

Pasquali, D., Miceli, C., Belgiovine, G., Rea, F., Mastrogiovanni, F., Sandini, G. & Sciutti, A. (2024). Artificial cognition, from the ground up. 1, 2, 3, 4, 16, 24, 26, 29

Pasquali, D., Garello, L., Belgiovine, G., Eldardeer, O., Lastrico, L., Rea, F., Mastrogiovanni, F., Sandini, G. & Sciutti, A. (2025). No robot is an island: An always-on cognitive architecture for social context awareness in dynamic environments. In *2025 IEEE International Conference on Development and Learning (ICDL)*, 1–8, IEEE. 1, 2, 3, 4, 5, 6, 7, 8, 15, 16, 19, 24, 25, 26, 27, 29, 62, 64

Pasquali, D., Rea, F., Morasso, P., Sandini, G. & Sciutti, A. (2026). ISEED: An always-on cognitive architecture for experience-driven interaction-oriented humanoid robots. *Frontiers in Neurorobotics*, **20**, 1920808. 1, 2, 3, 4, 6, 7, 8, 21, 24, 61, 62, 63, 64

Patompak, P., Jeong, S., Nilkhamhang, I. & Chong, N.Y. (2020). Learning proxemics for personalized human-robot social interaction. *International Journal of Social Robotics*, **12**, 267–280, published online 25 May 2019. 17

Pekarek Rosin, T., Hassouna, V., Sun, X., Krohm, L., Kordt, H.L., Beetz, M. & Wermter, S. (2025). A framework for adapting human-robot interaction to diverse user groups. In *Social Robotics*, vol. 15563 of *Lecture Notes in Artificial Intelligence*, 24–38, Springer Nature Singapore. 17

Petzschner, F.H., Garfinkel, S.N., Paulus, M.P., Koch, C. & Khalsa, S.S. (2021). Computational models of interoception and body regulation. *Trends in Neurosciences*, **44**, 63–76. 8, 20

Pezzulo, G., Parr, T. & Friston, K. (2024). Active inference as a theory of sentient behavior. *Biological Psychology*, **186**, 108741. 20

Pinto-Bernal, M., Biondina, M. & Belpaeme, T. (2025). Designing social robots with llms for engaging human interaction. *Applied Sciences*, **15**, 6377. 17, 18, 60

Raggioli, L., D'Asaro, F.A. & Rossi, S. (2025). Deep reinforcement learning for robotic approaching behavior influenced by user activity and disengagement. *International Journal of Social Robotics*, **17**, 903–915, published online 7 September 2023. 15, 17

Rodríguez, L.F. & Ramos, F. (2015). Computational models of emotions for autonomous agents: Major challenges. *Artificial Intelligence Review*, **43**, 437–465, published online 29 December 2012. 14

Rosado, O.G., Amil, A.F., Freire, I.T. & Verschure, P.F.M.J. (2022). Drive competition underlies effective allostatic orchestration. *Frontiers in Robotics and AI*, **9**, 1052998. 8, 21, 65

Sandini, G., Metta, G. & Vernon, D. (2007). The iCub cognitive humanoid robot: An open-system research platform for enactive cognition. In M. Lungarella, F. Iida, J. Bongard & R. Pfeifer, eds., *50 Years of Artificial Intelligence*, Lecture Notes in Computer Science, 358–369, Springer Berlin Heidelberg. 23

Sandini, G., Sciutti, A. & Morasso, P. (2025). Mutual human-robot understanding for a robot-enhanced society: The crucial development of shared embodied cognition. *Frontiers in Artificial Intelligence*, **8**, 1608014. 2, 11, 24

Saunderson, S. & Nejat, G. (2019). How robots influence humans: A survey of nonverbal communication in social human–robot interaction. *International Journal of Social Robotics*, **11**, 575–608. 12, 60

Scheunemann, M.M., Salge, C., Polani, D. & Dautenhahn, K. (2022). Human perception of intrinsically motivated autonomy in human-robot interaction. *Adaptive Behavior*, **30**, 451–472. 21, 23, 59

Schulkin, J. & Sterling, P. (2019). Allostasis: A brain-centered, predictive mode of physiological regulation. *Trends in Neurosciences*, **42**, 740–752. 20, 37

Senft, E., Lemaignan, S., Baxter, P.E., Bartlett, M. & Belpaeme, T. (2019). Teaching robots social autonomy from in situ human guidance. *Science Robotics*, **4**, eaat1186. 17, 22

Shaghaghi, S., Aliasghari, P., Tripp, B., Anderson, B., Dautenhahn, K. & Nehaniv, C.L. (2024). Towards an interaction architecture for the iCub robot: Social gaze space model adaptation for social interaction. In *2024 IEEE-RAS 23rd International Conference on Humanoid Robots (Humanoids)*, 295–302, IEEE. 15

Sloman, A. & Chappell, J. (2005). The altricial-precocial spectrum for robots. In *Proceedings of the 19th International Joint Conference on Artificial Intelligence (IJCAI)*, 1187–1192, Morgan Kaufmann, Edinburgh, UK. 3

Stange, S., Hassan, T., Schröder, F., Konkol, J. & Kopp, S. (2022). Self-explaining social robots: An explainable behavior generation architecture for human-robot interaction. *Frontiers in Artificial Intelligence*, **5**, 866920. 14, 23

Sterling, P. (2012). Allostasis: A model of predictive regulation. *Physiology and Behavior*, **106**, 5–15. 20, 37, 60

Tanevska, A., Rea, F., Sandini, G., Cañamero, L. & Sciutti, A. (2020). A socially adaptable framework for human-robot interaction. *Frontiers in Robotics and AI*, **7**, 121. 17, 24

Thompson, S., Lew, A., Phanse, R., Huang, A., Stanish, E., Li, Y. & Vázquez, M. (2024). Predicting human intent to interact with a public robot: The people approaching robots database (PAR-D). In *International Conference on Multimodal Interaction*, 536–545, ACM, New York, NY, iCMI '24, November 4–8, 2024, San Jose, Costa Rica. 15

Tian, X., Li, W., Xu, B., Dong, H., Wang, Y. & Shen, H. (2026). ROMA: Real-time omni-multimodal assistant with interactive streaming understanding. 19

Tinbergen, N. (1951). *The Study of Instinct*. Oxford University Press, New York, NY. 19, 41, 60

Tong, Z., Song, Y., Wang, J. & Wang, L. (2022). VideoMAE: Masked autoencoders are data-efficient learners for self-supervised video pre-training. In *Advances in Neural Information Processing Systems*, vol. 35, 10078–10093. 19

Vernon, D. (2014). *Artificial Cognitive Systems: A Primer*. MIT Press, Cambridge, MA. 2

Wang, C., Hasler, S., Tanneberg, D., Ocker, F., Joublin, F., Ceravola, A., Deigmoeller, J. & Gienger, M. (2024). LaMI: Large language models for multi-modal human-robot interaction. In *Extended Abstracts of the CHI Conference on Human Factors in Computing Systems*, 1–10, ACM. 18

Wang, R. (2026a). Human modalities in human-robot interaction: A review from multimodal and foundation model perspectives. TechRxiv preprint posted 26 February 2026. 18

Wang, R., Zhao, D., Suh, D., Yuan, Z., Chen, G. & Min, B.C. (2025). Personalization in human-robot interaction through preference-based action representation learning. In *2025 IEEE International Conference on Robotics and Automation (ICRA)*, 7377–7384, IEEE. 17

Wang, Y., Xu, Y., Nikolova, A., Wang, Y., Wang, J., Wang, C. & Tong, X. (2026b). How do we research human-robot interaction in the age of large language models? a systematic review. In *Proceedings of the 2026 CHI Conference on Human Factors in Computing Systems*, 1–28, ACM. 17, 18, 60

Yoshida, N., Sprekeler, H. & Gutkin, B. (2025). Linking homeostasis to reinforcement learning: Internal state control of motivated behavior. *Current Opinion in Behavioral Sciences*, **66**, 101611. 21, 60

Zhang, Y., Sun, P., Jiang, Y., Yu, D., Weng, F., Yuan, Z., Luo, P., Liu, W. & Wang, X. (2022). ByteTrack: Multi-object tracking by associating every detection box. In *Computer Vision – ECCV 2022*, 1–21, Springer Nature Switzerland. 30